

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-2-35W

Company- SKELLY OIL CO.
Farm- M. I. Severns No. 1

SEC. 15 T. 2 R. 35W
NW NW SW

Total Depth. 4970'
Comm. 10-26-59 op. 11-11-59
Shot or Treated.
Contractor. Sterling Drllg. Co.
Issued. 3-12-60

County Rawlins
KANSAS



CASING:

8 5/8" 450' cem w/300 sx.

Elevation. 3202' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand, gravel, clay & shale	460
shale	2045
sand & shale	2755
shale, anhydrite & chalk	2850
shale & redbed	3175
shale & lime	4065
lime	4240
lime	4270
shale & lime	4415
lime	4598
shale, lime & sand	4850
shale & lime	4925
lime	4970
Total Depth	

TOPS:	
Niobrara	1225
Fort Hayes	1626
Carlile	1733
Greenhorn	1901
Dakota	2047
Morrison	2650
Permian	2820
Stone Corral	3058
Chase	3203
Council Grove	3444
Admire	3750
Wabaunsee	3852
Topeka	3933
Oread	4040
Lansing	4146
Marmaton	4444
Cherokee	4592
Cherokee Sand	4657
Mississippian	4822
Arbuckle	4951

DST #2 4250-4270', op 1 1/2 hrs., good blow thruout test. Rec. 120' of salt water w/a few specks of oil & 1920' salt water. IFP 165#, FFP 925#, HP in 2240#, HP out 2115#, SIP 1365#/30 mins.

DST #3 4338-4356', op 1 hr., weak blow first 5 mins., then died. Rec. 2' of drilling mud, no shows. IFP 0#, FFP 0#, HP out 2230#, SIP 0#/30 mins.

Ran Schlumberger Survey.

DST #1 4202-4240', op 1 hr, strong blow thruout, rec. 2650' of salt water and no oil. IFP 435#, FFP 1255#, HP 2185#/ HP out 2130#, SIP 1345#/30 mins.