

Myers Trust #1-30X

Operator: Murfin Drilling Company, Inc.

Contractor: Murfin Drilling Company, Inc. Rig #3

KCC

OCT 12 2000

CONFIDENTIAL

610' FSL 1210' FEL

Sec. 30-2S-41W

Cheyenne County, Kansas

DST #1 4486-4544 OREAD, 30-45-60-90; IF: wk blow building to 8" in the bucket; FF: wk blow building to 6" in the bucket; Rec. 40' M, 170' WCM, (70% W), 520' SW, chl 57,000 ppm, chl, RW .15 @ 75°; HP: 2158-2123; FP: 143/263, 265/354; SIP: 1278-1246; BHT 148°.

DST #2 4535-4608, 30-45-30-45; IF: wk ¼" blow built to 1"; FF: wk surface blow, steady throughout; Rec. 60' clean oil, 26° grav., 60' OCM (10% O); HP: 2185-2179; FP: 28/36, 56/63; SIP: 162-1227; BHT 133°.

DST #3 4602-4662, 30-45-45-60; IF: wk surface blow built to ½"; FF: no blow; Rec. 29' OCM (4% O, 96% M), 1' FO; HP: 2251-2224; FP: 21/27, 30/34; SIP: 1001-714; BHT 136°.

DST #4 4742-4801, 30-30-30-30; IF: wk ¼" blow died in 25 min.; FF: no blow; Rec. 10' M; HP: 2375-2339; FP: 17/21, 23/27; SIP: 1048-960; BHT 137°.

DST #5 4810-4870 LANSING K ZONE, 30-45-45-60; IF: wk surface blow building to 1½"; FF: wk steady blow; Rec. 170' MW (80% W), 360' W, (46,000 ppm chlorides), RW .18 @ 65; HP 2412-2374; FP: 23/99, 113/209; SIP: 1386-1381; BHT 149°.