

90155

A-6-79

MAP NO. K-82 ELEV. 3193 KB 3189 DF
STATE Kansas COUNTY Stanton SEC. 10 Twp 30S Rge 39W
OPERATOR Pan American LOC. NE SW
WELL NO. 1 FARM NAME Baughman GU "J" FT. FROM _____ LINE _____
BL Unnamed (PD 5800) FT. FROM _____ LINE _____
FR. 4-21-61 SPUD 4-21-61 COMP. 5-29-61

CONT./GEOL. Barbour

NAME PRODUCING INTERVAL		COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a	<u>Morrow</u>	<u>5554-56</u>	<u>16</u>	<u>7000Ac, F/10x8</u>
b				
c				
d				

I. P. OIL/DIST.		WTR	WHOF	GAS	1010	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"	"	"	"
c	"	"	"	"	"	"	"	"
d								

SIP# 860 FI TP # _____ FI CP# _____ SIBHP _____
GOR. _____ GR. _____ PBDT 5608 TD 5700

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>1708</u>	<u>1050</u>			
<u>4 1/2"</u>	<u>5637</u>	<u>395</u>			

OPERATOR Pan American WELL NO. #1 Baughman GU "J" ELEV. 3193 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Council Grove	2706	4487
			Pennsylvanian	3058	
			Missouri	3909	
			Des Moines	4544	
			Morrow	5222	-2029
			Morrow Sand	5537-71	-2344
			Chester	5590	2397
			Ste. Genevieve	5636	2443

Spud 4-21-61, 8 5/8" @ 1708 w/1050 sx.

@ 4780, ran logs.

WLT #1 (Council Grove) @ 3068, op 1 hr, no rc, ISIP 0/5 mins, FP 0-50, FSIP 49/30 mins.

WLT #2 (Council Grove) @ 2996, op 1 hr, Rc 1320 cc wtr/NS, ISIP 688/30 mins, FP 0-100, FSIP 700/30 mins.

RTD 5700, logs. 4 1/2" @ 5637 w/395 sx. MICT. CO to 5608.

P/16/Morrow/5554-56, 1000 Ac, Frac 10,000 wtr X 8000 sd, 2" tbg @ 5537, Ga 492 MCF + 5 BL/NT, FCP 275, 6000 Ac, Rc 1d & SW (70,000 ppm). Shut in for press build up, 15 1/2 hr SITP 740, SICP 850, Ga 76 MCF + 1 BWPH (74,000 ppm)/NT, 12 hr SITP

600, SICP 800, Ga 68 MCF (no wtr), FCP 260, SIP 800, Ga 88
MCF. FCP dec to 250. 61 hr SIP 640.

IP WHOF 1010 MCF, SIP 860/24 hrs (Est deliverability 225 MCF
against 700# line pressure), fr Morrow 5554-56.

LIBERAL ELECTRIC LOG TOPS

3192 KB

Winfield 2398 (+794)
Council Grove 2648 (+544) WLT wtr
Heebner 3834 (-642)
Toronto 3848 (-656)
Lansing 3926 (-734)
Marmaton 4544 (-1352)
Morrow 5228 (-2036)
"S-3" 5536 (-2344) 4/24, g 1010 MCF ϕ
Chester 5598 (-2406)
Ste. Gen 5664 (-2472)
TD 5700