

KANSAS

IMPORTANT!
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 007 — 21,073
County Number

Operator

Rupe Oil Co., Inc.

Address

P. O. Box 2273 Wichita, Kansas 67201

Well No.

#1

Lease Name

Shaw Farms

Footage Location

660 feet from (N) ~~XX~~ line 1320 feet from (E) ~~XX~~ line

Principal Contractor

Red Tiger Drilling Co.

Geologist

William G. Clement

Spud Date

1-28-81

Date Completed

4-30-81

Total Depth

3035


P.B.T.D.

2848

Directional Deviation

None

Oil and/or Gas Purchaser

S. 6 T. 30 R. 12 ~~W~~Loc. N2 SECounty Barber640 Acres
N

Locate well correctly

Elev.: Gr. 1846DF _____ KB 1851

Top of Cement - 2210' CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8-5/8"	20	286	Common	225	2% Gel & 3% C
Production	7-7/8"	4½"	10.5	2875	50-50 Pozmix	150	18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	—	2788-90

TUBING RECORD

Size	Setting depth	Packer set at
2-1/16"	2787	---

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/11 bbls. 15% MCA & 30,000 SCF N ₂	2788-90

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
		Flowing			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	100	50	bbls.
			MCF		CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
SIGW			2788-90		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

JAN 14 1981

Operator
RUPE OIL COMPANY, INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Gas

Well No.

1

Lease Name

Shaw Farms

S 6 T 30 R 12 ^KW

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 2764-99 - 30-45-125-75 GTS in 8", Gauged 44 MCF increased to 71 MCF in 30". 2nd Opening gauged 109 MCF increased to 116 MCF in 5"; Gradually decreased to 65 MCF & Stabilized for 1 hr. Rec. 90' Gas cut watery mud & 1075' gas cut salt water. ISIP 1008#; IFP 82-173#; FFP 136-355#; FSIP 981#.			Indian Cave Wabaunsee Tarkio	2773 2828 2973
Electric Logs: GR-N, Guard & Caliper RTD 3035 LTD 3037				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

RUPE OIL COMPANY, INC.

William G. Clement
Signature

William G. Clement, Petroleum Geologist
Title

November 17, 1981.
Date

marked "original" then Geo. Survey & Hous. 11/16/81.