

Side TWO Rupe Oil Company, Inc.
 OPERATOR

LEASE NAME Hull

SEC 12 TWP 30S RGE 12W (W)

WELL NO #1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

| Formation description, contents, etc. | Top | Bottom | Name | Depth |
|--|-----|--------|---------------------|----------------|
| <p>Check if no Drill Stem Tests Run. <input checked="" type="checkbox"/></p> <p>Check if samples sent Geological Survey. <input type="checkbox"/></p> <p><u>DRILLERS LOG</u></p> <p>Sand & Shale 0</p> <p>Shale 330'</p> <p>Lime & Shale 1754'</p> <p>Lime 2790'</p> <p>RTD 3000'</p> <p>DST #1 <u>2750 - 2790</u></p> <p>30 - 60 - 30 - 90</p> <p>Rec: 420' muddy water</p> <p>ISIP 738#, IFP 46-102#,</p> <p>FSIP 903#, FFP 74-120#.</p> <p>E. Log, Great Guns GR-N, Guard & Caliper</p> <p>If additional space is needed use Page 2</p> | | | Base Florence Flint | 2246' (-407') |
| | | | Red Eagle Lime | 2636' (-797') |
| | | | Indian Cave | 2752' (-913') |
| | | | Wabaunsee | 2813' (-974') |
| | | | Tarkio Lime | 2953' (-1114') |
| | | | Total Depth | 3000' (-1161') |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|-------------|--------|----------------------------|
| Surface | 12 1/4" | 8 5/8" | 20# | 265' | Common | 190 SX | 2% gel 3% ccl |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

LINER RECORD

PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|---------------|-------------|--------------|---------------|-------------|----------------|
| TUBING RECORD | | | | | |