

2-30-14W

F. G. HOLL COMPANY

6427 EAST KELLOGG - P.O. BOX 780167
WICHITA, KS 67278-0167

ALEXANDER #1-2
85'N of C S2 S2 SW
Sec 2-30s-14w
Barber County, KS

15-007-22400

RELEASED

1996

JUN 10 1994

DST INFORMATION

FROM CONFIDENTIAL TO CONFIDENTIAL

DST #1 LOG: 3054-3063 LANGDON SAND
1) Slid tool 12', WB, Flush, WB
REC: 130' DM
MISRUN: Plugged Tool

DST #5 LOG: 4615-4627 ARBUCKLE
1) Losing Mud: Packer Failure
REC: 720' DM, Slight show of oil on bottom recorder
MISRUN: Packer Failure

DST #2 LOG: 3814-3864 DOUGLAS SAND
1) GBOB in 5", decreasing
2) NB, Flush, SB decreasing NB.
Times: 30"60"60"90"
REC: 180' SGCM (4%G)
240' SG&WCM (6%G)
210' SG&WCM (6%G)
630' Total Fluid
IHP: 1798 IFP: 211-212:30" ISIP: 425:60"
FHP: 1785 FFP: 250-376:60" FSIP: 1582:90"
BHT: NA CHL: 21,000 ppm

DST #6 LOG: 4152-4168 LKC "H" ZONE--Straddle Test
1) Losing Mud: Packer Failure
REC: 960' DM
MISRUN: Packer Failure

DST #3 LOG: 4462-4494 VIOLA
1) GBOB in 3"
2) GBOB in 3"
Times: 30"60"60"90"
REC: 1970' GIP
240' SG&WCM
120' SGCMW
360' Total Fluid
IHP: 2185 IFP: 110-111:30" ISIP: 1304:60"
FHP: 2177 FFP: 139-154:60" FSIP: 1315:90"
BHT: 119F CHL: 59,000 ppm

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 15 1992
OBSERVATION DIVISION
WICHITA, KS

DST #4 LOG: 4499-4529 SIMPSON SAND #1 & #2
1) SBOB in 1"
2) FBOB dead in 28"
Times: 30"60"60"90"
REC: 120' GIP
180' SGCWM
300' SGCWM
2170' SCGW
2650' Total Fluid
IHP: 2362 IFP: 866-1200:30" ISIP: 1253:60"
FHP: 2220 FFP: 1251-1266:60" FSIP: 1266:90"
BHT: 121F CHL: 69,000 ppm