

State Kansas Field \_\_\_\_\_  
 County HASKELL  
 Company C.S.O.  
 Farm Iholf "A" Well No. 1  
 Sec. 14 Twp. 30S Range 32W  
 fr N fr E fr S fr W  
 of 100' 54W of C  
 Contractor \_\_\_\_\_

Remarks \_\_\_\_\_  
 Comm. 7-8-53 Comp. 8-7-53  
 Elev. 2873 T. D. 2765 P. B. \_\_\_\_\_  
 Pay 2678-2704, 2648-60

I. P. 4.050 mcf R. P. 403.9  
 Casing Record: 13 3/8 7  
 20 10 3/4 5 1/2 2764/500  
 16 8 5/8 594/300

	RTD 2765 run	Tops
	log	
	ROCT & CO.	
	Ø 70/ 2722-36 no g no wtr	
A/200	frac/1000 sd/500	kerd/1000 H <sub>2</sub> O/850
	500' of H <sub>2</sub> O in hole in 14 hrs.	
	swab & A/500	H <sub>2</sub> O/1500 swab 35 gal of H <sub>2</sub> O/hr.
	set ret @ 2710 & pg. w/100 at	
	pull thg & swab dry	
	Ø 130/ 2678-2704 no g no wtr	
	60/ 2648-60 " " "	
	run thg w/plw & frac (2648-2660)	
A/100	frac/1500 sd/950	H <sub>2</sub> O/1500
	frac (2678-2704) w A/100	kerd/200
	frac/2500 sd/1200	
	blew <del>400</del> 1,180 mcf & 3pts H <sub>2</sub> O	

Blew 1040 mgf @ 1 qt h<sub>2</sub>O

Wash w/ 1000 gal emulsed sol h<sub>2</sub>O/500

Blew 860 mgf @ 1 1/2 pts. h<sub>2</sub>O/min

Emulsed sol/500 SI for 1 1/2 hrs & backed  
off and gauged 744 mgf

Final test 7 2/20 4,050 mgf SIP 403.9