

27-30-15W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GREAT LAKES CARBON CORP.
Farm "Massey "B" No. 3

SEC. 27 T. 30 R. 15 W
SE NE SE

Total Depth. 4363'
Comm. 9-7-46 Comp. 11-24-46
Shot or Treated.
Contractor. R. C. Patton Co.
Issued. 12-28-46

County. Barber
KANSAS



Elevation. 1780 feet

Production. Dry

CASING:

8 5/8" 815' Cem.
5 1/2" 4329' Cem.

Figures Indicate Bottom of Formations.

lime rock	10
red bed	95
shale red	265
red bed & shale	545
red bed	612
Anhydrite	623
red bed, shale	740
shale	848
shale & shells	1570
shale " salt	1680
anhydrite & shale	1690
lime " shale	1888
shale & shells	1915
anhydrite & shale	1975
lime & shale	2080
shale & shells	2175
lime " shale	2579
shale	2830
shale " shells	2945
shale	3060
lime " shale	3135
lime	3564
lime & shale	3798
sand	3810
lime	3812
lime & shale	3973
lime	4017
lime " shale	4175
lime	4190
lime & shale	4229
lime	4283
lime & shale	4315
lime	4363

Total Depth

Sample Tops:
Heebner 3689
Douglas 3761

Casing 3892 Sample & Sch.
Base K. C. 4228 Sample & Sch.
Massey Zone 4334 Sample & Sch.
good por., good sat.