

8-30-15W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY NADEL & GUSSMAN

SEC. 8 T. 30 R. 15W

FARM Moffett

NO. 1

LOC. NE NE SE

TOTAL DEPTH 4871 P.B. 4600

COMM. 11-5-50


COMP. 11-28-50

COUNTY Barber

SHOT OR TREATED

CONTRACTOR Glenn Peel Drilling Co., Inc.

ISSUED 3-10-51



CASING

10 3/4" 551' cem.
5 1/2" 4688' cem.

ELEVATION 1956 (m)
1958 RB (2nd)

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay & sand	90
shale & red bed	280
shale & shells	824
shale	862
anhydrite	905
shale & shells	1250
shale	1620
shale & shells	1997
lime	2278
lime with shale strks	2330
lime	2600
lime & shale	3005
shale, lime & shells	3135
shale	3205
shale & lime	3420
shale	3430
lime	3495
lime & shale	3725
lime	3838
lime & shale	4055
lime	4415
lime with broken strks	4513
lime	4560
lime, shale & chert	4620
cherty lime.	4665
lime	4695
lime, shale & chert	4728
shale & chert	4750
lime	4800
lime & shale	4828
lime	4871

Total Depth
P. B. 4600

Lansing	4065
Cherty Congl.	4590
Maquoketa Shale	4610
Viola	4620
Simpson Shale	4765
Artuckle	4845

Scout Tops:	
Heebner	3851
Brown Lime	4046

