

COPY

Vess Oil Corp.

ATTACHMENT TO ACO-1

Page 1 of 2

Francis-Massey #1-26
Approx. NW NW 26-30S-15W
Barber County, KS

API #15-007-22449

DST #1 4042-4085 **ZN** Lansing
Times: 30-30-30-30
Blow: Built to 7-1/2" on 1st
 open - Built to 5-1/2" on
 2nd open
Rec: 140' MW (30% mud, 70% water)
 83,000 cc
IFP: 67-67 FFP: 101-105
ISIP: 1461 FSIP: 1450
HP: 2034-2001 Temp 110 Degrees

DST #2 4260-4296 **ZN** Dennis
Times: 30-30
Blow: 1/4" blow-1st open
Rec: 20' TWM
IFP: 56-45 FFP: ----
ISIP: 1461 FSIP: ----
HP: 2134-2123 Temp 110 Degrees

DST #3 4383-4429 **ZN** Marmaton
Times: 30-45-45-60
Blow: BOB-1-3/4 min. - 1st open
 2-3/4" - 2nd open
Rec: 440' GIP
 56' SOGCM (5% gas, 2% oil, 93% mud)
IFP: 56-56 FFP: 56-78
ISIP: 67 FSIP: 78
HP: 2234-2201 Temp 116 Degrees

DST #4 4432-4500 **ZN** Marmaton
Times: 30-30
Blow: Weak blow-died in 26 min.
Rec: 10' Mud (oil specks in tool)
IFP: 67-56 FFP:
ISIP: 67 FSIP:
HP 2263-2256 Temp 116 Degrees

RECEIVED BY THE STATE OF OKLAHOMA
DEPARTMENT OF REVENUE

JAN 3 1985

RECEIVED BY THE STATE OF OKLAHOMA
DEPARTMENT OF REVENUE