

State Kansas County Sumner

Company Messman-Rinehart Oil Co. Well No. 1


Farm Orie Love

Survey _____

Block No. _____ Sec. 16 Twp. 30 S Range 2 W

Co-Ord. _____ Elev. 1337 KB
1335 DF

SE SE NW



Contr: White & Ellis Drlg.

25% - Messman-Rinehart Oil Co

25% - Chicago Group

50% - A. A. Seeligson, Jr.

Pan Amer. FO & DHM (\$4,000)
AM 2-2407

3800' Miss. test to be comm.
by 11-1-58

NOTE: Show Sketch of Lease and Well Location in Above Space

2310 Ft. from N. Line _____ Ft. from S. Line _____

2310 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
10-17-58		M.I.R.T. - Spud
		8-5/8" @ 283' w/175 sx. cem.,
		2% gel, P.D. @ 8:30 A.M.
		10/18/58
10-19		SUS @ 5:00 a.m.
10-20	1350	Drlg.
10-21	2125	Drlg.
10-22	2675	Drlg.
10-23	3112	Drlg.

Date	Depth	692595
	3062	K.C. (-1725) (54' down hole corr.)
	3130	Drlg.
10-24	3262	Drlg.
	3280	Drlg. (Latta Pool Zone 3228-40 - very ft. SO, no odor, no flourescense, no kick on machine
10-25	3483	Trip (#16 bit)
	3270	Base K.C. (-1933)
10-26	3699	Miss. (cherty dolo) (-2362) SO & odor
	3711	DD
DST #1 -3701-11 - Op 1 hr., Gas to surf. in 63" (smell when tool closed) Rec. 157' fluid,: 112' O&GCM 45' mdy oil 157'		
BHP (30") 1496-1032#, FP 30-65#, HHd (1997#)		
	3797	R.T.D. (Sj. Log) D & A 10/28/58