

RECEIVED
JAN 06 2004
KCC WICHITA

WELL REPORT

McCoy Petroleum Corporation
Unruh 'A' #1-32
NW NW
Section 32-30S-18W
Kiowa County, Kansas
API #15-097-21,522

MPC #786 (03-32)

Spud Date: 10-10-03

Alford Prospect

Contractor: Sterling Drilling Company, Rig #4

Geologist: David Clothier

Elevations: 2176' GL 2185' KB (All measurements from KB)

09-30-03 The Rathole Company set 80' of 20" conductor. Will use water well drilled for Cobb A #1.

10-09-03 MIRT.

10-10-03 TD 320'. Drilling 12 1/4" hole. Spud well at 4:30 AM. Drilled to 750'. Ran 18 joints new 8 5/8" 23# casing. Tally = 731.20'. Set at 742' KB. Acid Services cemented with 220 sacks A-Con and 100 sacks Common. Plug down at 6:30 pm. Cement circulated. Strapped bottom 3 joints and welded collars on 15 joints.

10-11-03 TD 870'. Drilling ahead.

10-12-03 TD 1940'. Drilling ahead. Gas detector on undersurface at 1200'.

WELL REPORT

McCoy Petroleum Corporation
Unruh "A" #1-32
NW NW
Section 32-30S-18W
Kiowa County, Kansas

RECEIVED

JAN 06 2004

KCC WICHITA

Page 2

10-13-03 TD 2610'. Drilling ahead.

10-14-03 TD 3060'. Drilling ahead. Deviation 3/4° @ 3050'. Bit trip @ 3050'.

10-15-03 TD 3520'. Running short trip. Deviation 1° @ 3520'. Displaced mud @ 3114'.

SAMPLE TOPS	<i>Structure compared to</i>	
McCoy Petroleum Corp Unruh "A" #1-32 NW NW Sec. 32-30S-18W KB: 2185'	McCoy Petroleum Corp Cobb "A" #3-29 80' N of NE SE NW 29-30S-18W KB: 2188'	McCoy Petroleum Corp Cobb "A" #2-29 W/2 NE 29-30S-18W KB: 2178'

Herington	2498 (-313)	+19	+ 4
Krider	2518 (-333)	+13	+ 2
Winfield	2588 (-403)	+ 7	- 9
Towanda	2648 (-463)	+12	- 5
Fort Riley	2710 (-525)	+ 9	- 6
Florence	2751 (-566)	+11	- 8
Wreford	2861 (-676)	+11	- 3
Co. Grove	2906 (-721)	+ 9	- 6
Cottonwood	3057 (-872)	+ 6	- 3
Neva	3096 (-911)	+13	- 1
Wabaunsee	3387 (-1202)	- 2	- 9
Stotler	3507 (-1322)	- 8	-22
Emporia			
RTD	3575		

Stotler Lime 3507-20': Ls., wht.-crm., f.- md. xltn., foss., 5% glauc., quest. gas bubbles, gd. intrxtln. por., 40 UGK, 5 UCHR.

WELL REPORT

McCoy Petroleum Corporation
Unruh "A" #1-32
NWNW
Section 32-30S-18W
Kiowa County, Kansas

RECEIVED

JAN 06 2004

KCC WICHITA

Page 3

DST #1 3511-3520' (Stotler Lime)
Open 30" SI 60" Open 60" SI 60"
1st Open: Fair built to B.O.B. in 23"
2nd Open: Weak built to 1 1/2" and stab.
(Tool slid 6' to bottom)
Recovered 186' of muddy water (10% mud, 90% water)
IFP 29-54# FFP 60-97#
ISIP 1157# FSIP 1056#

LOG TOPS	Structure compared to	
McCoy Petroleum Corp Unruh "A" #1-32 NWNW Sec. 32-30S-18W KB: 2185'	McCoy Petroleum Corp Cobb "A" #3-29 80' N of NE SE NW 29-30S-18W KB: 2188'	McCoy Petroleum Corp Cobb "A" #2-29 W/2 NE 29-30S-18W KB: 2178'

Herington	2517 (-332)	Flat	-15
Krider	2530 (-345)	+ 1	-14
Winfield	2599 (-414)	- 4	-20
Towanda	2662 (-477)	- 2	-19
Fort Riley	2722 (-537)	- 3	-18
Florence	2764 (-579)	- 2	-21
Wreford	2876 (-691)	- 4	-18
Co. Grove	2918 (-733)	- 3	-18
Cottonwood	3063 (-878)	Flat	- 3
Neva	3101 (-916)	+ 8	- 6
Wabaunsee	3388 (-1203)	- 3	-10
Stotler	3508 (-1323)	- 9	-23
LTD	3575		

WELL REPORT

McCoy Petroleum Corporation
Unruh "A" #1-32
NW NW
Section 32-30S-18W
Kiowa County, Kansas

RECEIVED

JAN 06 2004

KCC WICHITA

Page 4

10-16-03 RTD 3575'. LTD 3575'. Tripping out of hole second time for logs. Log-Tech running Dual Induction and Neutron Density logs. Acid services **plugged well** with heavy mud in hole and between all plugs using 110 sx of 60/40 Pozmix, 6% gel. Bottom plug @ 1100' with 50 sx, 2nd plug @ 750' with 50 sx and top plug @ 40' to surface with 10 sx. Plugged rathole with 15 sx. Plug down at 6:00 PM. Rig released at 6:30 PM.

Note: Great Plains hauled 550 bbls off reserve pit on 10/15/03.