

9-244W Map No. 2-84

OPER PAN AMERICAN PETR CORP - Liberal,
Ks.

WELL #7 LUCIENE BLACK "A"

DR Murfin Drlg.

FIELD Victory (KC-Des M & Mrw) Field

i.P. Co P 11 BOPD & 12 BWPD, St L 5493-97



S-T-R 18-30S-33W
SPOT C NE NE
CO HASKELL (Ks)
ELEV 2964 KB

(KB Log)

- Hb 4049-1085
- Tor 4069-1105
- Lan-A 4141-1177
- Lan-B 4195-1231
- 2nd Lan B zn 4406-1442
- KC-A 4600-1636
- KC-B 4657-1693
- Des M 4755-1791
- Mrw 5222-2258
- Mrw sd 5336-2372
- B/sd ^{1.4**} 5556-2592
- Chest 5370-2406
- Ste G 5394-2430
- St L 5492-2528
- LTD 5599-2635
- RTD 5600-2636

£ #1 (St L) 5500-10, R 10' gry-brn lt blue chert
£ #2 (St L) 5510-50, R 40' hard gry frac lm st, no sho
of por, no sho of staining, RTD 5600, Log, 5" @5567 w/
200 sx. & DV tool @4313 w/125 sx. ^{5.0}

MICT, CO 5524, Pf 16/5493-97 (St L), 250A (15%), §
1/2 BFPH (20% oil & 80% LW)/8 hrs, 2000A (15%), § 1½
BFPH (50% oil)/4 hrs, § 27 1/4 BFPH (60% oil)/24 hrs,
7500A (10%), § 1d, § 3 BO & 40 B-wtr/10 hrs, § 11½ BO & 10
BW/13 hrs, Set Plg @5448, Pf 8/5337-39 ⁵³ (Mrw), § dry, 250A
(15%), § on 1d - Re-Acid, 2000A (15%), § & flo 1d, Flo
1 BOPH & 1,930,000 Cfgpd/1 hr, SICP 220# - Ga 1,426,000
Cfgpd - dry, Sq 5337-39 w/150 sx., Pf 8/4787-89 (Des M),
§ dry - nat, 250A (15%), § 26 BF (4% oil & 95% wtr)/6 hrs,
2000A (15%), § 1d, § 12 BO & 38 BW/12 hrs w/tr gas, §
1.67 BOPH & 9.98 BWPH/4 hrs, 5000A (15%), § on 1d, § 13
BO & 6 1/4 BW/8 hrs - Sq Pfs 4787-89 w/175 sx., Pf 8/4143
5 (Lan), § dry, 250A (15%), § 5 1/3 BO & 33 1/2 BW/8

Data Inc

hrs, § 8 1/3 BO & 102 BW/NT, Sq 4143-45 w/ 150 sx., Pf 4/
4143-44 (Lans), 250A, § 1d, § 1 BO & 24 BW/8 hrs, § 2 1/2
BFPH (98% wtr)/4 hrs, Clor on wtr, 78,000 PPM,
§ 20 BF (98% wtr)/20 hrs, 2000A @4143-44, § 1d, § 220 BF
(99% wtr)/11 hrs, Sq 4143-44 w/175 sx., CO 5524, Ran 2 3/8" tbg @5513 (W111 prod
5493-97) - POP

P 1.16 BO & 17 BW/16 hrs, P 9½ BO & 12 BW/22 hrs, P 5 BO & 8 BW/16 hrs, P 11 BO &
12 BW/24 hrs - Co P 11 BOPD / 12 BWPD, St L 5493-97 - COMPLETED on 9-21-65

MISC DATA

GEOI 1-S ELEV 2961 DF SPUD DATE 7-20-65
FTG 2955 GR DRLG COMP _____
SUPPT _____ FR by DATA 7-19-65
CSG 8" @746 w/600 sx. 5" @5567 w/200 sx. COMP by 9-23-65

LIBERAL ELECTRIC LOG TOPS

2964 KB

Winfield 2686 (+278)

Heebner 4050 (-1086)

Toronto 4070 (-1106)

Lansing 4140 (-1176) ϕ 8 1/3 BO + 103 BW

"C" Zone 4406 (-1442)

"D" Zone 4598 (-1634)

Marmaton 4756 (-1792)

Pay Zone 4780 (-1810) ϕ 13 BO + 6 1/4 BW

Morrow 5220 (-2256)

"S-3" 5336 (-2372) 2/16; g 1,426 MCF

Chester 5356 (-2392)

Ste. Gen 5394 (-2430)

St. Louis 5492 (-2528) ϕ 11 BOPD + 12 BWPD

TD 5600