

12-333W Map No. *K-84*OPER PAN AMERICAN CORP - Liberal, Ks.S-T-R 18-30S-33WSPOT C NE NWCO HASKELL (Ks)ELEV 2964 KBWELL #1 ANTON UNIT "B"

Murfin Drlg.

FIELD Victory (Multi Pay) FieldI.P. P 95 BOPD & 2% wtr, Gr 39.3^o, Lans "A"4154-56

(KB Log - Welox)

Hb	4031	-1067
Tor	4054	-1090
Mo	4100	-1136
Lan-A	4128	-1164
Lan-B	4178	-1214
Lan zn	4396	-1432
KC-A	4588	-1624
KC-B	4648	-1684
Des M	4758	-1794
Mrw	5215	-2251
Mrw sd	5337	-2373
B/sd	5358	-2394
Chest	5359	-2395
Ste G	5379	-2415
St L	5474	-2510
LTD	5600	-2636

No DST's, RTD 5600, Log, 5½" @5600 w/200 sx. & DV tool @4715 w/200 sx.

CO 5560, Pf 20/5477-82 (St L), 500A (15%), § 1d, § dry - 3000A (15%), § 1d, § 1 BOPH & 1 BWPH/4 hrs
 § 4 BOPH & 12 BWPH/8 hrs, PB 5450, Pf 8/4649-51 (KC), Ga 100,000 Cfgpd, nat, 250A (15%), Ga 2,000,000 Cfgpd & 16 BLW/1 hr, Ga 1,341,000 Cfgpd (dry), FCP 630#
 3 hr Ga 1,666,000 Cfgpd w/tr oil & 6½ BWPH, PB, 4635, Pf 8/4588-90 (KC), 250A (15%), § 1d, § 3 BO & 113 BW/16 hrs
 Sq 4588-90 w/200 sx., PB 4400, Pf 8/4397-99 (Lans), § 45 BW w/sho gas and oil/15 hrs - Sq 4397-99 w/125 sx., Pf 8/4154-56 (Lans "A"), 250A (15%), § 1d, § 35 BO & 1 BW/10 hrs, § 3 BOPH & tr wtr/4 hrs, 500A (15%), § 1d, § 54 BO & 3 BW/16 hrs, CO 5450, 2 1/16" tbg w/pkr @4365 - 2nd string 2 1/16" tbg @4163, 500MCA @4649-51, § 1d, §

*win 2680 + 184**Data Inc*

no sho of oil, gas or wtr, 250 MA (15%), § 1d, no sho, Pull tbg from 4635, Set plg @4638, § 54 BO & 3 BW/6 hrs
 Lans "A" 4154-56, POP - State Pot: P 95 BOPD & 2% wtr, Gr 39.3 deg from Lans "A" 4154-56 - COMPLETED (12-22-65)

MISCEL DATA

GEOL Bob Cash*L-5* ELEV 2962 ~~DF~~SPUD DATE 10-24-65

FTG _____

2956 GR

DRLG COMP _____

SUPPT _____

FR by DATA 9-23-65CSG 8" @777 w/600 sx, 5½" @5600 w/200 sx.COMP by " 12-29-65

LIBERAL ELECTRIC LOG TOPS

*Revised
Able City Log*

2964 KB

*Neva 3288 (-324)
Heeb 4030 (-1066)*

- Winfield 2680 (+184) →
- Lansing 4128 (-1164) ⚡ 95 BOPD
- "C" Zone 4396 (-1432)
- "D" Zone 4586 (-1622)
- Marmaton 4758 (-1794)
- Pay Zone 4776 (-1814)
- Morrow 5216 (-2252)
- Sand 5336 (-2372) →
- Ste. Gen 5378 (-2414)
- St. Louis 5466 (-2502)
- Por 5556 (-2592)
- TD 5600

Chester 5359 (-2395)