


FORMATION

TEST

REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

Company VINCENT OIL CORPORATION Lease and Well No. #1 PARKIN Sec. 5 Twp. 30S Rge. 19W Test No. 1 Date 11/1/57

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE: 6/11/84
CUSTOMER: VINCENT OIL CORPORATION
WELL: 1 TEST: 1
ELEVATION (KB): 2320 FORMATION: KANSAS CITY
SECTION: 5 TOWNSHIP: 30S
RANGE: 19W COUNTY: KIOWA STATE: KANSAS
GAUGE SN #13552 RANGE: 4050 CLOCK: 12

INTERVAL TEST FROM: 4643 FT TO: 4674 FT TOTAL DEPTH: 4674 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 4638 FT SIZE: 6 5/8 IN PACKER DEPTH: 4643 FT SIZE: 6 5/8 IN
PACKER DEPTH: FT SIZE: IN PACKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WHEATSTATE
MUD TYPE: CHEMICAL VISCOSITY: 44
WEIGHT: 9.2 WATER LOSS (CC): 17.2
CHLORIDES (P.P.M.): 22000
JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? NO REVERSED OUT? NO
DRILL COLLAR LENGTH: 500 FT I.D.: 2 1/4 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 4122 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 21 FT TOOL SIZE: 5 1/2 OD IN
ANCHOR LENGTH: 31 FT SIZE: 5 1/2 OD IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 FH IN

BLOW: INITIAL FLOW PERIOD WEAK BLOW THROUGHOUT.
FINAL FLOW PERIOD FAIR BLOW INCREASED TO
STRONG BLOW.

RECOVERED: 570 FT OF: SALTWATER
RECOVERED: FT OF: CHLORIDES 108000 PPM
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:

REMARKS: READ BOTTOM CHART

TIME SET PACKER(S): 6:30 PM TIME STARTED OFF BOTTOM: 9:30 PM
WELL TEMPERATURE: 126 °F
INITIAL HYDROSTATIC PRESSURE: (A) 2419 PSI
INITIAL FLOW PERIOD MIN: 30 (B) 83 PSI TO (C) 181 PSI
INITIAL CLOSED IN PERIOD MIN: 45 (D) 1648 PSI
FINAL FLOW PERIOD MIN: 45 (E) 249 PSI TO (F) 323 PSI
FINAL CLOSED IN PERIOD MIN: 60 (G) 1647 PSI
FINAL HYDROSTATIC PRESSURE (H) 2330 PSI

PRESSURE DATA

RANGE: 19W COUNTY: KIOWA
GAUGE SN #13552 RANGE: 4050

STATE: KANSAS
CLOCK: 12

WELL TEMPERATURE: 126 °F
OPEN TOOL: 6:30 PM


FINAL CLOSED-IN PRESSURE: 60 MIN 60 MIN

PRESSURE BREAKDOWN


30

TKT # 4396

I




TKT # 4396



FORMATION

TEST

REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

Company _____ VINCENT OIL CORPORATION
Lease and Well No. _____ #1 PARKIN
Sec. 5 Twp. 30S Rge. 19W Test No. 2 Date 6/14/8

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE: 6/14/84
CUSTOMER: VINCENT OIL CORPORATION
WELL: 1 TEST: 2
ELEVATION (KB): 2320 FORMATION: MISSISSIPPI
SECTION: 5 TOWNSHIP: 30S
RANGE: 19W COUNTY: KIOWA STATE: KANSAS
GAUGE SN #13552 RANGE: 4050 CLOCK: 12

INTERVAL TEST FROM: 5068 FT TO: 5208 FT TOTAL DEPTH: 5208 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 5063 FT SIZE: 6 5/8 IN Packer DEPTH: 5068 FT SIZE: 6 5/8 IN
PACKER DEPTH: FT SIZE: IN Packer DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WHEATSTATE
MUD TYPE: CHEMICAL VISCOSITY: 43
WEIGHT: 9.2 WATER LOSS (CC): 21.2
CHLORIDES (P.P.M.): 25000
JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? NO REVERSED OUT? NO
DRILL COLLAR LENGTH: 90 FT I.D.: 2 1/4 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 4957 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 21 FT TOOL SIZE: 5 1/2 OD IN
ANCHOR LENGTH: 140 FT SIZE: 5 1/2 OD IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 FH IN

BLOW: INITIAL FLOW PERIOD WEAK BLOW INCREASED
TO FAIR.
FINAL FLOW PERIOD FAIR BLOW INCREASED
TO STRONG.

RECOVERED: 310	FT	OF: DRILLING MUD
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:
RECOVERED:	FT	OF:

REMARKS: READ BOTTOM CHART

TIME SET PACKER(S): 5:00 AM	TIME STARTED OFF BOTTOM: 8:00 AM
WELL TEMPERATURE: 130 °F	
INITIAL HYDROSTATIC PRESSURE:	(A) 2632 PSI
INITIAL FLOW PERIOD MIN: 25	(B) 145 PSI TO (C) 145 PSI
INITIAL CLOSED IN PERIOD MIN: 45	(D) 1750 PSI
FINAL FLOW PERIOD MIN: 45	(E) 159 PSI TO (F) 179 PSI
FINAL CLOSED IN PERIOD MIN: 63	(G) 1738 PSI
FINAL HYDROSTATIC PRESSURE	(H) 2525 PSI

400# 4397

I

4397



YKCT 4397



51