


S. 29 T. 30S R. 2 E
W

Loc. SE NE NW

County Sumner

640 Acres

N



Locate well correctly

Elev.: Gr. 1341

DF N/A KB 1347.5

KANSAS DRILLERS LOG

API No. 15 — 191 — 21110
County NumberOperator
Tenneco Oil CompanyAddress Suite 139, Ciudad Bldg., 3000 United Founders Blvd.
Oklahoma City, Okla. 73112Well No. 1-29
Lease Name StrunkFootage Location
1650 feet from (N) (S) line 2310 feet from (E) (W) linePrincipal Contractor
Slawson #5

Geologist —

Spud Date
Sept. 20, 1980Total Depth
3300'P.B.T.D.
2918'Date Completed
Nov. 15, 1980Oil Purchaser
N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	347'	Class H 60/40 POZ	100 200	1/4% Flocele 3% Cacl
Production	7-7/8"	5-1/2"	15.5#	2959'	Class H	120	10% Nacl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
—	—	—	1	N/A	2814-24
TUBING RECORD					
Size 2-3/8"	Setting depth 2790'	Packer set at 2790'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1250 gal. 15% KCL	2814-24

INITIAL PRODUCTION

Date of first production 11-15-80	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 7 bbls. Gas — MCF Water 90 bbls. Gas-oil ratio — CFPB
Disposition of gas (vented, used on lease or sold) None	Producing interval (s) 2814-2824

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Tenneco Oil Company DESIGNATE TYPE OF COMP.: OIL, GAS,
Oil DRY HOLE, SWDW, ETC.:

Well No. 1-29 Lease Name Strunk

S 29 T 30S R 2 E W

WELL LOG
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Harrington	684			
Cottonwood	1184			
Wabaunsee	1814			
Topeka	2092			
Heebner	2502			
Stahlnaker	2810			
Kansas City	3136			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

Allen B. Ashley
Signature
Administrative Supervisor
Title
December 3, 1980
Date