

**WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS**

CASING RECORD

NW NE SW
LOCATION 990' W & 330' S of NE cor of SW/4 SEC 9 T 30 R 2 W.

10" 2059 FARM Love NO. 1 COUNTY Sumner
20" 8 1-4 2782 COMPANY Champlin Refining Co.
15 1-2 94 6 5-8 2830 CONTRACTOR
12 1-2 816 5 3-16 COMMENCED 7/28/27. COMPLETED 5/15/29.
TOTAL DEPTH 3201'. SHOT QUARTS BETWEEN
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 7/27/1929. Deepening Record.

ELEVATION
INITIAL PRODUCTION
50 bbls.

Formation	Depth	Formation	Depth	Formation	Depth
gray slate cellar	8	blue brkn. lime	1105	gray lime	2383
gray slate	13	gray lime	1115	dark slate	2386
sandy lime HFW	35	blue brkn. lime	1130	gray lime	2390
blue slate	45	gray lime	1160	dark slate	2400
red rock	50	drk brkn. lime	1165	gray lime	2410
blue slate	60	hard lime gray	1185	blue slate	2424
red rock	65	red rock	1187	gray lime	2437
blue slate	85	light lime	1220	dark slate	2450
white lime	110	broken lime	1275	brkn. drk slate	2490
blue slate	150	blue shale	1285	sand	2540
slate shelly	175	brkn. sdy lime	1308	brkn. sand	2583
blue shale	220	white sdy lime	1327	blue slate	2637
blue slate	240	5 BW PH 1308-1313'		gray lime	2652
red rock	245	brkn. lime slate	1345	dark slate	2734
blue slate	265	gray lime	1353	gray lime	2740
dark shelly	280	gray brkn. lime	1370	blue slate	2746
white salt	305	blue shale	1400	Gas show 2746'	
white lime	325	light sdy lime	1420	gas sand	2756
blue slate	335	gray lime	1425	blue shale	2758
white lime	350	blue shale	1470	gas sand blue	2770
white salt	410	gray lime	1475	2 M. gas 2756'	
blue slate	415	shale	1485	Inc. 3 M. 2758-2760'	
white lime	425	gray lime	1520	blue shale	2782
blue slate	430	light sand	1550	sandy shale	2810
white lime	470	blue brkn shale	1585	gray shale	2825
gray lime slate	543	sand	1607	blue slate	2848
gray lime	570	drk brkn. lime	1693	sand	2878
gray slate	573	gray lime	1718	blue shale	3023
white lime	610	gray brkn. lime	1766	lime	3037
gray lime	635	1 BW PH 1766'		Oil lime	3049
lime shell blue slate	655	dark lime	1785	Show oil 3037	
blue slate	665	brkn. lime	1790	Oil inc. 3039'	
white lime	685	white lime	1800		
slate lime brkn drk	730	black shale	1810	Log missing	3050
blue slate	740	drk brkn. lime sand	1870	sand	3051
white lime	750	white lime	1885	lime	3143
slate	765	drk brkn. lime	1895	slate	3147
pink lime	770	sand water	1910	lime	3201
gray lime	783	gray lime	1918	Oil 3197-3200	
gray gas sand	795	blue slate	1925		
gray lime	805	drk brkn lime sand	1935	TD	3201'
brkn lime & sand	821	blue slate	1942		
gray lime	865	gray sand	1957		
brkn lime	875	blue slate	1978		
lime sandy gray	915	light lime HFW	2011		
drk brkn. lime	925	sand light	2036		
light brkn. slate	940	Good gas show 2015'			
red rock	945	lime white	2116		
gray brkn. lime	960	blue slate	2135		
gray lime	965	gray lime	2162		
red shale	970	blue slate	2170		
blue shale	975	black slate	2175		
Small show gas 975'		gray lime	2182		
lime light	1020	drk slate	2205		
2 BW PH 1020'		gray brkn. lime	2230		
dark slate	1024	sand water shelly	2330		
red rock	1032	lime	2350		
light lime	1050	dark slate	2370		
blue slate	1070	gray lime	2375		
gray lime	1090	dark slate	2378		