

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KAN SAS


Location NW SE NW
990' fr SL 990' fr EL NW/4

Sec. 9 T.30 R.27.

Casing Record

County- Sumner.

20" 10" 2307 Farm- Latta No. 5-B.
15 3/8" 76 8 1/2" 2789 Company- Champlin Ref. Co.
12 3/8" 1358 65/8" Contr.-
12 3/8" 1358 53/16" Comm.- 9/19/28. Comp.- 1/9/29.
Total Depth 3096'. Shot Quarts



Correspondence Regarding This Well Should Be Referred to

Elevation

Figures Indicate Bottom of Formations.
Date Issued. 1/19/29.

Initial Production 20 bbls.

Formation	Depth	Formation	Depth	Formation	Depth
cellar	9	shale	1361	slate	2445
red rock	20	lime	1366	lime	2452
blue shale	55	slate	1375	shale	2465
sandy lime	65	lime	1385	lime	2470
blue shale	85	slate	1395	slate	2475
red rock	90	lime	1405	lime	2515
blue shale	235	shale	1420	slate	2525
red rock	270	lime	1427	lime shells	2580
blue shale	290	slate	1450	sand	2625
salt	345	lime	1457	Water 2585'	
shale blue	375	blue slate	1498	slate	2777
salt	420	lime	1505	lime	2780
lime	435	slate	1520	sand	2870
slate & salt	520	brkn lime	1540	Gas show 2798	
lime	575	blue slate	1555	shale drk	3065
lime & shale	595	sandy lime	1565	lime	3096
lime	615	slate	1652	Oil	3082
slate	625	lime	1657		
lime	645	slate blue	1705	Total Depth	3096'
lime & slate	800	lime	1707		
red rock	805	slate	1724		
lime & slate	880	lime	1745		
lime	955	slate	1753		
Water at 925'		lime	1760		
red rock	965	slate	1794		
lime & slate	1015	lime	1811		
sandy lime	1025	slate	1814		
Water 1015-25'		lime	1830		
lime	1040	slate	1895		
red rock	1050	gray lime	1924		
lime	1070	sand	1935		
slate	1082	(1 M. gas)			
gray lime	1087	lime	1962		
blue slate	1095	slate blue	1967		
lime	1105	sandy shale	2007		
slate	1110	lime	2050		
lime	1120	Show gas 2018			
red rock	1125	HF ^W 2028'			
gray lime	1155	slate	2150		
red rock	1165	lime	2154'		
lime	1175	slate	2164		
blue slate	1190	lime	2167		
lime	1200	slate	2180		
shelly slate	1230	lime	2225		
lime	1235	HF ^W 2230-60'			
slate	1245	slate	2242		
lime	1270	sandy shale	2280		
drk slate	1283	sand	2386		
lime	1294	slate	2389		
red rock	1300	lime	2402		
brkn lime	1320	slate shelly	2422		
lime	1325	lime	2431		
sandy lime	1351	slate	2439		
lime gray	1357	lime	2443		