



DATE: 04/25/95
 TIME: 10:31:40
 PAGE: 21

LEASE CODE #: 340216
 LEASE: BATES UNIT WELL: 5-04
 FIELD: BATES , RESERVOIR : MISS
 COUNTY: SUMNER , STATE: KS
 OPERATOR: PHILLIPS PETROLEUM CO

PHILLIPS - PRODUCTION - L E D G E R

DATE	OIL, BBL	CUM-OIL	GAS, MCF	CUM-GAS	GOR, CF/BBL	WATER, BBL	WATER CUT, %	DAYS ON
PRIOR	57,904	57,904	0	0	0	56,500	49.39	3998
1/93	87	57,991	0	0	0	611	87.54	31
2/93	78	58,069	0	0	0	552	87.62	28
3/93	88	58,157	0	0	0	612	87.43	31
4/93	80	58,237	0	0	0	597	88.18	30
5/93	86	58,323	0	0	0	595	87.37	30
6/93	76	58,399	0	0	0	597	88.71	30
7/93	77	58,476	0	0	0	617	88.90	31
8/93	81	58,557	0	0	0	641	88.78	31
9/93	93	58,650	0	0	0	699	88.26	30
10/93	93	58,743	0	0	0	722	88.59	31
11/93	92	58,835	0	0	0	699	88.37	30
12/93	89	58,924	0	0	0	722	89.03	31
TOT/93	1,020	58,924	0	0	0	7,664		
1/94	86	59,010	0	0	0	682	88.80	31
2/94	78	59,088	0	0	0	549	87.56	28
3/94	86	59,174	0	0	0	608	87.61	31
4/94	80	59,254	0	0	0	588	88.02	30
5/94	78	59,332	0	0	0	608	88.63	31
6/94	75	59,407	0	0	0	587	88.67	30
7/94	78	59,485	0	0	0	589	88.31	31
8/94	74	59,559	0	0	0	589	88.84	31
9/94	72	59,631	0	0	0	570	88.79	30
10/94	71	59,702	0	0	0	589	89.24	31
11/94	70	59,772	0	0	0	570	89.06	30
12/94	72	59,844	0	0	0	589	89.11	31
TOT/94	920	59,844	0	0	0	7,118		
1/95	72	59,916	0	0	0	589	89.11	31
2/95	61	59,977	0	0	0	532	89.71	28
3/95								
4/95								
5/95								
6/95								
YTD/95	133	59,977	0	0	0	1,121		
TOTAL	59,977	59,977	0	0	0	72,403		

McGee Energy Services, Inc. and Clients
 makes no representation or warrants with
 respect to any of this information.

101 N. Robinson
Oklahoma City, Okla 3

April 27, 1982



INTER-OFFICE CORRESPONDENCE SUBJECT:

Phillips Petroleum Company
Bates Unit 5-4
NW NW NE Sec. 36-30S-2W
Sumner County, Kansas

MEMO TO: FILE

FROM: T. R. Moore

Phillips Bates Unit 5-4
Elevations: 1324 KB
1323 DF
1318 GL

RTD: 3810'
Ran Dresser Atlas Electric Logs

ELECTRIC LOG TOPS

Heebner	2454	(-1130)
Lansing	3076	(-1752)
Base Kansas City	3306	(-1982)
Marmaton	3386	(-2062)
Cherokee	3570	(-2246)
Mississippi	3726	(-2402)

Set 5 1/2" casing at 3805, PBD 3768.
Perforated (Miss) 3756 - 62, 2 HPF, acid, Swbd 3.75 BF (60% oil) with GSG.
Completed (12/21/81) IPP 46 BO + 15 BWPD.

RECOMPLETION POSSIBILITIES

Lansing - Kansas City
3262-71 Limestone, Ooclastic, fair porosity,
fluorescence, streaming cut

Wellsite Geologist: H. L. Collins

TM:ld

McGee Energy Services, Inc. and Clients
makes no representation or warrants with
respect to any of this information.