

MAR 17 1977

**KANSAS DRILLERS LOG**

S. 8 T. 30 R. 2 ~~XX~~ W

API No. 15 — 191 — 20613  
County Number

Loc. NE SW NW


Operator  
Cities Service Oil Company

County Sumner

Address  
209 E. William, 700 Sutton Pl. Bldg., Wichita, Kansas 67202

640 Acres  
N

Well No. 5 Lease Name Latta "A"



Footage Location  
1650 feet from (N) (E) line 990 feet from (E) (W) line

Locate well correctly  
Elev.: Gr. 1299'

Principal Contractor Gabbert-Jones, Inc. Geologist Herb Johnson, Well Site

Spud Date 8/13/76 Total Depth 3254' P.B.T.D. 3220'

Date Completed 8/22/76 Oil Purchaser Derby

DF 1322' KB 1327'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	301'	50/50 Pozmix	225	2% CaCl <sub>2</sub>
Production	7-7/8"	5-1/2"	14#	3256'	Class "A"	150	10% Salt 75% CFB

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
-----	-----	-----			
<b>TUBING RECORD</b>			2	1/2"	3188-98'
Size	EUE	Setting depth	Packer set at		
2-3/8" OD		3185'	None		

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
250 Gal. 15% HCL Acid	3188-98'
500 Gal. 15% NE Acid	3188-98'

MAR 17 1976

**INITIAL PRODUCTION**

Date of first production <u>10/25/76</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil <u>10</u> bbls.	Gas <u>MCF</u>	Water <u>15</u> bbls.	Gas-oil ratio <u>CFPB</u>
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Cities Service Oil Co.

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Well No. 5 Lease Name Latta "A" Oil

S 8 T 30 R 2 E  
W

**WELL LOG**


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Log Attached				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

  
Signature W. J. Devaney  
Region Operations Manager  
Title  
10/20/76  
Date

H01178

8-30-20

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Latta "A" #5  
Seic 8-30S-2W  
Summer County Kansas

Commenced: 8-13-76

Completed: 8-22-76

Operator: Cities Service Oil Co.

Depth		Formation	Remarks
From	to		
0	303	Shale-Shells	Ran 7 jts of 8 5/8" csg set @ 301' Cemented @/225 sks 50/50 Posmix 2% CC PD @ 12:45 a.m. 8-14-76
303	500	Shale-Shells	
500	735	Lime	
735	1005	Lime-Shale	
1005	1212	Shale-Shells	
1212	1515	Lime-Shale	
1515	1912	Shale-Lime	
1912	2190	Lime-Shale	Ran 82 jts of 14# J-55 set @ 3252 w/150 sks class A 10% Salt .75% CFR-2 PD @ 8:45 p.m. 8-22-76
2190	2650	Lime	
2650	2730	Shale	
2730	2825	Sand	
2825	3254	Lime	
	3254 - TD		

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

  
JAMES S. SUTTON II

Subscribed and sworn to before me this 26th day of August, 1976.

  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.