


4-279W MAP NO. 2-84 SEC. 20-30S-33W
 STATE Kans COUNTY Haskell LOC. C SW NW
 OPER. Pan American Petr. Corp - Liberal, Ks. FT/FR _____ LINE _____
 WELL 3 FARM L.T. Williams FT/FR _____ LINE _____
Lemon North (Multi Pay) ELEV. 2963 GR. 2969 DF 2972 KB _____
 CONT. Murfin Drlg. GEOL. _____



F.R. 2-25-65 SPUD 3-20-65 COMP. 4-29-65
 TD. 5501 FM. Ste G PBD. _____
 COMP. RECORD
Lans "A" 4140-43 12 2250A
Co P 25 BOPD & 200 BWPD
8 5/8" @783 w/750 sx 5 1/2" @5390 w/175 sx.

Data Inc.

(KB Log) No DST's, No Cores, RTD 5500, Ran Log,
 Hb 4046 -1074 5 1/2" @5390 w/175 sx. & DV tool @4512 w/
 Tor 4070 -1098 150 sx., Pf 16/5328-32 (Mrw sd), no sho
 Lans-A 4140 -1168 nat, 250A (15%), \$ ld, \$ dry, no sho,
 Lans-B 4190 -1218 2000A (15%), \$ ld, no sho, PB 5300, Pf
 2nd Lans-B 8/4415-17 (Lans), no sho nat, 250A (15%),
 4440 -1468 \$ ld, \$ 5 BWPB, no sho/11 hrs, Clor
 KC-A 4589 -1617 82,000 PPM, Sq 4415-17 w/175 sx., PB 4405,
 Des M 4589 -1783 Pf 8/4148-50 (Lans"A"), no sho nat, 250A
 5230 -2258 (15%), \$ ld, \$ 3 BO & 45 BW/14 hrs, Clor
 Mrw sd 5326 -2354 96,000 PPM, \$ 4 BO & 12 BW/8 hrs, 500A (15%
 B/Mrw sd 5335 -2363 (15%), \$ ld, \$ 4 BO & 17 BW/4 hrs, Sq
 Chest 5354 -2382 4148-50 w/150 sx., Pf 12/4140-43 (Lans,
 Ste G 5382 -2410 "A"), no sho nat, 250A (15%), \$ ld, \$ 2
 LTD 5501 -2529 BWPB/3 hrs, 2000A (15%), \$ ld, \$ 6 BO &
 RTD 5500 -2528 184 BW/14 hrs, Clor 86,000 PPM, \$ 36 BO &
240 BW/24 hrs, \$ 25 BO & 200 BW/24 hrs,
2 3/8" tbg @4132, POP, Co P 25 BOPD & 200 BWPD, Lans 4140-43 -
COMPLETED (4-23-65)

