

90007

11-228W+ 84
MAP NO. SEC. 21 TWP. 30S RGE. 33W
STATE Kans COUNTY Haskell LOC. C SE NW

OPERATOR Pan American Petroleum Corp. (Ulysses, Ks) FT. FROM LINE

WELL NO. 1 FARM NAME U. V. Anton "B" FT. FROM LINE

LEMON ELEV. 2952 GR. 2959 DF. 2961 KB

FR. 9/17/62 SPUD. 9/16/62 COMP. 11/20/62

CONT. Big Chief Drlg. Co. /GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
Lans	4142 A	Abr Jet	250 A
Morr	5334-36 S3	16	500 A & Frac

	*		

d I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.

b State Pot (Lans) Pump 30 BO + 160 BW (Grav. 37.4°) ..24

c Est Del. (Morr) 1600 Mcfgpd CP 700# SIP 1195# ..24

d (DUAL COMPLETION - LANS & MORR)

D & A ()

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBD. 5441 TD 5600

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	DEPTH	W/SAX.
8 5/8" @	752	700		
5 1/2" @	5470	280		

OPERATOR Pan American Petr Corp WELL NO. U. V. Anton "B" ELEV. 2961 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
(5600' Gas Tst)			KB Tops & Datums:		
RTD (St Lou)	5600	-2639	Chase	2624	+ 337
			C.G.	2916	+ 45
RTD 5600, Sj Log.			Penn	3280	- 319
WLT #1 (Lans "B") A 4195 1/2':			Tor	4036	-1075
Op 1 hr, R 3600 cc Wtr,			Mo	4116	-1155
ISIP 1030#/13", SP less			Lans "A"	4140	-1179
than 50", FSIP 1030#/12".			Lans "B"	4183	-1222
WLT #2 (Morr) 5338' S3 Op 70",			KC "A"	4771	-1810
R 20,600 cc filt Wtr,			Chero	4938	-1977
ISIP 1600#/NT, FSIP 1600#/ 50".			Morr	5227	-2266
			Chest	5358	-2397
5 1/2" @ 5470' w/280 sx, CO 5441,			Ste Gen	5422	-2461
S3 Perf 16/5334-36 (Morr), 500 MA			St Lou	5536	-2575
+ Frac (10,000 GW + 10,000# Sd), 5 hr Ga 3,957 Mcfgpd thru			LTD	N.A.	
2" Tbg, Pkr @ 5200, Perf 16/ A. 4193-95 (Lans), \$ 255 BFW/8 1/2 hrs. Sqz 4193-95 w/100 sx.					

CO 5200, Abra-jet @ 4142^A (Lans), \$ ld, \$ 30 GO/2 hrs,
A/250, \$ ld, \$ 45 BO + 126 BW/NT, 2 7/8" T @ 4153,
POP. P 7 BO + 100 BW/16 hrs, P 28 BO + 72 BW/20 hrs,
P 18 BO + 94 BW/22 hrs (G. 37°), P 22 BO + 109 BW/24
hrs, P 30 BO + 109 BW/24 hrs (Lans). Pull Pump, CO 5441,
Tbg w/pkr @ 4474, Dual Complete from Lans & Morrow.
State Pot: Pump 30 BOPD + 79% wtr, G. 37.4°, Lans @ 4142.
WHOF g 3,000 MCF, Est Del. 1,600 MCFPD, 700# CP,
SIP 1195/24 hrs, Morrow 5334-36, 11/6/62.

LIBERAL ELECTRIC LOG TOPS

2961 KB

Winfield 2696 (+265)
Heebner 4056 (-1095)
Toronto 4072 (-1111)
Lansing 4140 (-1179) ϕ P 30 BOPD + 79% wtr
Lansing "D" 4594 (-1633)
Marmaton ~~4722~~ (-1761) -1809 *Amavillo*
Morrow 5227 (-2266)
Sand 5312 (-2351) ϕ g 3,000 MCF ; (20/44)
Chester (Opr) 5358 (-2397)
Ste. Gen 5394 (-2433)
TD 5600 *St Louis 5490 (-2529)*