

8-112W

MAP NO.

84

DUAL COMP

21-30S-33W

STATE Kansas COUNTY Haskell LOC. C NW NW

OPER. Pan American Pet Corp - Ulysses, Kansas FT/FR LINE

WELL 2 FARM U.V. Anton "B" FT/FR LINE

Lemon ELEV. 2954 GR. 2960 DF. 2963 KB

SUNT Big Chief GEOL.

CO. INT. 5600' Morr Test

F.R. 3-20-63 SPUD. 3-21-63 COMP. 8-13-63

TD 4800 FM. Des Moines PBTD. 4714

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
	Lans "A" A	4137-39			8
i.p. Lans "B" A	4191-93			8	250A
Dual Completion - State Pot: (Lans "A") Cal P 92					
BOPD + 28 BWPD (Gr 39.2 deg), (Lans "B") P 59 BOPD					
+ 22 BWPD (Gr 38.1 deg) 8 5/8" @729 w/400 sx. - 5 1/2" 4748					

Casing Record	(KB Log)				
	Chase	2622	+ 341	Lans "G"	4420 -1457 w/200 sx.
	CG	2912	+ 51	KC "A"	4596 -1633
	Penn	3256	- 293	"B"	4648 -1685
	Tor	4068	-1105	Des M	4761 -1798
	Mo	4112	-1149	LTD	NA
	Lans "A"	4136	-1173	RTD	4800 -1837
	* Lans "B"	4190	-1227		

RTD 4800, Log, 5 1/2" @4748 w/200 sx., CO 4714 PBTD, 8/4191-93 A  
 (Lans "B"), \$ 100 BLW - no show, 250A, \$ 60 BO + 30 BW/9 hrs,  
 8/4137-39 (Lans "A"), PB 4150, \$ 11 BLW - no show, 250A, \$  
 1d, \$ 35 BO + 12 BW/4 hrs, CO 4714, 2 1/16" tbg w/pkr @4175, 2  
 1/16" tbg @4155, POP, P 64 BO + 3 BW/15 hrs, Lansing "B" 4191-  
 93, \$ 30 BO + 12 BW/4 hrs, Lansing "A" 4137-39, State Pot:  
 P 59 BOPD + 22 BWPD, Gravity 38.1 deg., Lansing "B" 4191-93 A  
 State Pot: (8 hr pump rate) Cal P 92 BOPD + 28 BWPD, Gr 39.2  
 deg. Lansing "A" 4137-39 - Dual Completion - COMPLETED  
 (8-6-63)

LIBERAL ELECTRIC LOG TOPS

2963 KB

Winfield 2694 (+269)

Council Grove 2930 (+33)

Heebner 4050 (-1087)

Toronto 4064 (-1101)

Lansing 4136 (-1173) \$ 60 BO + 30 BW ("A-1")

\$ 35 BO + 12 BW ("A")

"D" Zone 4595 (-1632)

Marmaton 4760 (-1797)

TD 4802