


90069

83
87

8-270W / MAP NO. _____ SEC. 22-30S-34W
STATE Kans COUNTY Haskell LOC. 150' W of C SE NE
OPER. Pan American Pet Corp - Box 432 - Liberal, Ks. FT/FR _____ LINE _____
WELL 1 FARM Hague FT/FR _____ LINE _____
COL WC ELEV. 2925 GR. 2934 DF. 2936 KB. _____
CONT Helmerich & Payne GEOL. Bob Cash
CO. INT. 5600' Test
F.R. 6-10-64 SPUD. 6-12-64 COMP. 8-25-64
TD. 5900 FM. Salem PBTD. _____



COMP. RECORD

WC-1 1/2 mi SE of Satanta (Mrw Oil) Pool
8 5/8" @1759 w/1250 sx. 5 1/2" @4815 w/175 sx.

D&A

Data Inc.

(KB Log)			DeMo	4687	-1751
CG	2831	+ 105	Mrw	5192	-2256
Penn	3224	- 288	Mrw sd not called		
Tor	4003	-1067	St G	5300	-2364
Mo	4050	-1114	St L	5412	-2476
Lan-A	4084	-1148	Salem	5589	-2653
"-B	4140	-1204	LTD	5900	-2964
"-F	4349	-1413			
KC-A	4530	-1594			
"-B	4592	-1656			

RTD 5900 (in Salem), no tests, Sj log
WLT #1 (St G) 5379 1/2-82, Op 2 hrs, R 3500 cc wtr (10% fm wtr),
NSO/G + 1.2 cu ft shot gas, ISIP 1900#/39", SP less than 50#,
FSIP 1800#/38"
WLT #2 (KC-A) 4532-34 1/2, Op 2 hrs, R 2.11 cu ft shot gas + .99 cu
ft free gas + 3400 cc wtr w/sli flour, ISIP 1475#/43", SP
less than 50#, FSIP 1300#/58"
WLT #3 (DeMo) 4726 1/2-29, Op 2 hrs, R 4.3 cu ft free gas + 1.05
cu ft shot gas + 1.2 cu ft sd gas + 3800' cc wtr (17% fm
wtr), ISIP 1625#/30", FSIP 1500#/60"
WLT #4 (KC-B) 4596 1/2-99, Op 2 hrs, R 1.18 cu ft shot gas, NSO/G
+ 6700 cc wtr (24% fm) w/flour, ISIP 1250#/20", FSIP 1300#/30"
WLT #5 (Lans-A) 4086-88 1/2, Op 2 hrs, R 3800 cc wtr, NSO/G, ISIP
1175#/43", FSIP 1150#/31", 5 1/2" @4815 w/175 sx., MICT, Pf
16/4726-28 (De Mo), \$ dry, 250A, \$ ld, \$ 1 BWPH w/SS dead oil +
sho gas/6 hrs, Clor 130,000 PPM, 2000A, \$ ld, Rec ld, no help, PB
4710, 8/4533-35 (KC-A), 250A (15%), \$ ld, Rec ld, \$ dry, NS,
2000A (15%), Rec ld w/good sho gas, TSTM, Sq 4533-35 w/100 sx.,
CO 4710, Pf 8/4533-35 (KC-A), \$ dry nat, 250A, \$ ld, \$ 2 1/2 BWPH
w/dead oil scum/9 hrs, 2000A (15%), \$ ld, \$ 260 BW/13 hrs, Clor
127,000 PPM, Sq 4533-35 w/100 sx., Perf 8/4412-14 (Lans-A), \$

dry, A/250, \$ 107 BldW/NT, \$ 3 BO + 13 BW (cl₂ 89,000)/8 hrs,
A/1500 (15%), rec ld, \$ 1 BOPH + 3 BWPH/4 hrs, \$ 6 BO + 30
BW/8 hrs, pl @ 4100, Perf 8/4086-88 (Ians "A"), \$ 24 BW w/
show dead oil/8 hrs, \$ 27 BW w/scum dead oil/9 hrs, Sq/4086-88/
100 sx, CO 4515, CO 4116, Perf 8/4112-14 (Ians "A"), A/250 (15%)
\$ ld, \$ 26 BW w/scum oil/8 hrs, \$ 31½ BW w/oil scum/NT, Sq/
4112-14/100 sx, CO 4514, Perf 8/4152-54 (Ians), \$ dry,
A/250, \$ ld, \$ 55 BW/2 hrs, CO 4710, Perf 8/4596-97 (KC-B)
\$ dry, no show nat, A/250 (15%), rec ld, \$ dry, A/1000, rec ld,
\$ 70 BW/14 hrs; D & A.

LIBERAL ELECTRIC LOG TOPS

2936 KB

Winfield 2615 (+321)
Council Grove 2851 (+85)
Heebner 3981 (-1045)
Lansing 4083 (-1147) Tst XW&SO
Marmaton 4688 (-1752)
Morrow 5190 (-2254)
Fault
Ste. Gen 5303 (-2367) WLT XW
St. Louis 5453 (-2517)
Spergen 5686 (-2750)
Osage 5832 (-2896)
TD 5900 D & A