

6-125W

MAP NO.

84

SEC. 24-30S-34W

STATE Kansas

COUNTY

Haskell

LOC C NE SE

OPER. Pan American Pet. Corp., Liberal, Kansas

FT/FR

LINE

WELL #1 FARM Garner Unit "B"

FT/FR

LINE

COL Victory

ELEV 2955

GR. 2962

DF 2965

KB

CONT. Big Chief Drlg. Tools

GEOL.

CO. INT. 4900' Marm test

F.R. 3/9/64

SPUD

3/25/64

COMP.

6/9/64

TD. 4902

FM.

Des Moines RTD 4872

COMPLETION RECORD PROD. FM.-I.P. PROD. INTERVAL & TREATMENT	PRODUCING FM.	FROM	TO	PERF. W/HOLES	TREATMENT
	Lans "A"	4126	- 28	16	3250A
	Des Moines	4743	- 45	16	3250A

Data Inc.

State Pot: (Lans) Pump 39 BOPD & 15% wtr (Grav. 38.1 deg.)

Co. Ga: (Des Moines) 1,174,000 Cfgpd

DUAL COMPLETION

SIZE	DEPTH	SAX	SIZE	DEPTH	SAX
8-5/8" @	750 w/700 sx.				
5 1/2" @	4900 w/200 sx.				

OPER. Pan American Pet. Corp., Liberal, Ks. SEC. 24-30S-34W

WELL #1 Garner Unit "B"

ELEV 2965KB LOC C NE SE

KB Log Tops:					
CG	2880	/ 85	Lans "A"	4124 -1159	Kc "A" 4576 -1611
Penn	3260	- 295	Lans "B"	4162 -1197	Kc "B" 4650 -1685
Tor	4044	-1079	Lans "F"	4393 -1428	Des M 4741 -1776
					LTD 4902 -1937

No DST's, RTD 4900 (Des M), SJ Log, 5 1/2" @ 4900 w/200 sx.
 CO 4872, GRN Log, Pf 16/4743-45, (Des M) \$ dry nat, 250A (15%)
 Rec ld, Ga 600,000 Cfgpd/1 hrs, 3000A (15%) Flo ld, Ga 1,174,000
 Cfgpd/6 hrs (no wtr, no oil) 16/4143-45 (Lans "A") PB 4285, \$ dry
 Nat, 250A (15%) \$ 66 BO/21 hrs, Grav. 38 deg., \$ 2-1/3 BOPH, NW
 5 hrs, 1000A (15%) Rec ld, \$ 25 BO & 75 BSW, Clor 112,000 PPM
 /17 hrs, Sq 4143-45 w/125 sx., 4 way jet 4142-42 1/2 (Lans "A")
 \$ dry nat, 500A (15%) \$ ld, \$ 220 SW/19 hrs, \$ 10 BSWPH w/scum
 oil/8 hrs, Sq 4142-42 1/2 w/150 sx., Pf 16/4126-28 (Lans "A") 250A
 (15%) \$ ld, \$ 3 BO & 8 BWPH/16 hrs, \$ 3 1/4 BFWPH (90% SW/4 hrs)
 Clor 80,000 PPM, 1000A (15%) \$ ld, \$ 1/2 BO & 1/2 BWPH/5 hrs, 2000A
 (15%) \$ ld, \$ 1/2 BO & 1/2 BWPH/5 hrs, 2000A (15%) \$ ld, \$ 4 BO & 2
 BWPH/5 hrs, Clor 100,000 PPM, SD, Storm, CO 4872, 2-1/16" tbg
 w/Pkr @ 4730, 2-1/16" tbg @ 4119, POP, State Pot:) 39 BOPD & 15%
 Wtr, Grav. 38.1 deg., Lans "A" 4126-28, Ga 1,174,000 Cfgpd,
 Des M 4743-45, DUAL COMPLETION Completed (6/3/64)

LIBERAL ELECTRIC LOG TOPS

2965 KB

Winfield 2664 (+301)

Heebner 4022 (-1057)

Toronto 4046 (-1075)

Lansing 4122 (-1157) \$ XW; ¢ \$ 4 BOPH + 2 BWP/4 hrs.

"D" Zone 4574 (-1609)

Marmaton 4730 (-1765) ¢ g 1,774 MCF