


7-40W MAP NO. 84 24-30S-34W  
 STATE Kansas COUNTY Haskell SEC C SW NE  
 OPER Pan American Pet. Corp., Liberal, Kansas LOC  
 WELL #2 FARM R. B. Garner FT. FR  
 VICTORY, Ext. ELEV 2959 GR 2966 FT. FR 2969  
 Big Chief Drlg. Tools GEOL. Robert Cash  
 5600' Miss test  
 FR 5/6/64 SPUD 5/9/64 COMP 7/7/64  
 TD 5603 FM St Louis PSTD 4563



PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
Lans	4129	- 31	16	250A
Co. Pump 100 BOPD plus 20 BWPD (Gr 37 deg.)				

Completion Record  
 Casing Record  
 8-5/8" @ 778 w/600 sx.  
 5 1/2" @ 5600 w/175 sx. DV tool @ 4850 w/200 sx.

*Data Inc.*

KB Log Tops:								
CG	2882	f	87	Kc B	4648	-1679	Ste G	5366 -2397
Tor	4051		-1082	Des M	4732	-1763	St L	5470 -2501
Lans A	4128		-1159	Mrw	5222	-2253	LTD	5603 -2634
Lans B	4170		-1201	Mrw sd	5294	-2325	RTD	5600 -2631
Lans F	4397		-1428	B/" "	5304	-2335		
A	4584		-1615	Chest	5342	-2373		

RTD 5600, No DST's, SJ Log, 5 1/2" @ 5600 w/175 sx. DV tool @ 4850 w/200 sx., CO 5573, Pf 24/5560-63 (St L) Swb dry, no sho, nat, 250A (15%) Rec ld, Swb dry, no sho, 2000A (15%) Swb ld, Swb 2 BO plus 11 BWP/11 hrs, Clor 120,000 PPM, PB 5400, PF 16/5298-5300 (Mrw) 250A, Swb ld, no sho in 6 hrs, Frac (7500 GW x 5000# sd) Swb 260 B ld, Ga 696,000 Cfgpd/15 hrs, Ga 696,000 Cfgpd plus 108 B ld/24 hrs, Plug 5270, 16/4586-88 (Kc "A") Swb dry, 250A (15%) Swb Ld, Swb 2 BSWPH/2 hrs, Clor 127,000 PPM, Swb 11 BSWPH/4 hrs, no sho oil or gas, Sq 4586-88 w/125 sx., 16/4129-31 (Lans "A") Swb 87 BFW/4 hrs, Swb 16 BWP w/SSO&G/4 hrs, Clor 145,000 PPM, Sq 4129-31 w/100 sx., CO & Set Plug 4563, 16/4129-31 (Lans "A") Swb dry, 250A, Swb Ld, Swb 22 BO & 15 BW/6 hrs, Grav 37 deg. Clor 88,000 PPM, Swb 20 BO & 8 BW/5 hrs, Co. P 100 BOPD plus 20 BWPD, 37 deg. Gr. from Lans 4129-31, COMPLETE (6/30/64)

Correction: (5/27/64) By Operator - Was: #1 R. B. Garner  
 Is: #2 R. B. Garner