

2-94W MAP NO. K-84 SEC. 24-30S-34W
 STATE Kans COUNTY Haskell LOC. C SW SE

OPER. Pan American Pet Corp - Liberal, Ks. FT/FR _____ LINE _____

WELL 4 FARM R.B. Garner 2956 2963 FT/FR _____ LINE _____

COL Victory Ext ELEV. 2963 GR. 2971 DF 2973 KB _____

CONT. Big Chief Drlg. GEOL. No Geol on test

CO. INT. _____


F.R. 8-3-64 SPUD 8-9-64 COMP. 2-11-65

TD. 4908 FM. Des M PBD. 4807

RECORD Des M 4768-70 8 250A

Est P 20 BOPD & 10 BWPD

8 5/8" @802 w/500 sx. 5 1/2" @4840 w/225 sx.



Data Inc.

(KB Log) No DST's, No Cores, RTD 4900, Log, 5 1/2"
 CG 2885 / 88 @4840 w/225 sx., PF 8/4768-70 (Des M), \$
 Penn 3276 - 303 dry - nat, 250A, \$ 1d, \$ 35 BO & 17 BW/
 Tor 4060 -1087 18 hrs, SSG, Gr 38 deg., MP pkr @4755,
 Mo 4108 -1135 PF 8/3157-59 (Lans "A"), \$ no sho nat,
 Lan-A 4134 -1161 250A (15%), R 1d, \$ 2 BO & 29 BW/8 hrs,
 "B" 4176 -1203 \$ 3 BO & 75 BSW/24 hrs, 500A (15%), \$ 1d,
 KC-A 4600 -1627 \$ 2 BO & 66 BW/16 hrs, \$ 3 1/2 BFPH w/tr
 "B" 4662 -1689 oil/6 hrs, Clor 98,000 PPM, Pkr @4150, Pf
 Des M 4747 -1774 8/4139-41 (Lans "A"), 250A (15%), \$ 1d,

LTD 4908 -1935 \$ 28 BW/9 hrs, \$ 3/4 BO & 4 1/2 BW/4 hrs,
 Clor 95,000 PPM, \$ 10 BO & 74 BW/24 hrs, Sq,
 PF 4139-41 w/100 sx., Pf 8/4135-37 (Lans "A"), 250A (15%), \$
 1d, \$ 1 BWPH w/sho oil/3 hrs, Clor 75,000 PPM, 1000A (15%), Rec
 1d, \$ 5 BO & 70 BW/15 hrs, \$ 6 BO & 126 BW/24 hrs, Sq 4135-37
 w/125 sx., CO 4159, Pf 4/4158 (Lans "A"), \$ dry - nat, 250A (15%)
 \$ 1d, \$ 3 1/2 BWPH - no sho oil/3 hrs, \$ 84 BW/24 hrs, Sq 4158 w/
 100 sx., Pf 8/4147-49 (Lans "A"), 250A (15%), \$ 1d, \$ 90 BW/12
 hrs, Clor 80,000 PPM, Sq 4147-49 w/175 sx., Pf 8/4135-37 (Lans
 "A"), 250A, \$ 1d, \$ 156 BW, no sho oil/6 hrs, 2 7/8" @4181, P
 4 BO & 88 BW/16 hrs, P 1 BO & 80 BW/24 hrs, P no oil & 70 BW/16
 hrs, P 1 BO & 24 BW/24 hrs, P Averg 1 BOPD & 40 BWPD/4 days, last
 test P 1/2 BO & 29 BW/24 hrs, P no oil & 32 BW/24 hrs, P 1/2 BO & 39
 BW/24 hrs, Sq 4135-37 w/175 sx., CO 4807, 2 7/8" tbg @4776, \$
 1 3/4 BOPH & 3/4 BWPH/NT from 4768-70 (Des M), POP, (Sq 4157-59),
 Est Co P 20 BOPD & 10 BWPD, Des M 4768-70 (All Lans zns Sq off)

COMPLETED (2-9-65)

LIBERAL ELECTRIC LOG TOPS

2760 KB

Winfield 2666 (+300)

Heebner 4040 (-1074)

Toronto 4056 (-1090)

Lansing 4134 (-1168)

"C" 4406 (-1440)

"D" 4600 (-1634)

Marmaton 4764 (-1780) ϕ Est. 20 BOPD + 10 BWPD

TD 4908