

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 025 — 20373
County NumberOperator
Ladd Petroleum CorporationAddress
P. O. Box 2848, Tulsa, Oklahoma 74101.Well No. 1 Lease Name
RooneyFootage Location
330 feet from (N) line 330 feet from (E) line NE/4Principal Contractor
Raines and Williamson Geologist
John Curtis

Start Date July 16, 1980 Date Completed July 27, 1980 Total Depth 5450 P.B.T.D. None

Directional Deviation 2° Max. 1° T.D. Oil and/or Gas Purchaser
None


JUL 23 1980

CONFIDENTIAL

State Geological Survey
WICHITA BRANCHS. 2 T. 30 R. 25 X
W

Loc. C NW NW NE

County Clark

640 Acres
N

Elev.: Gr. 2576

DF 2583 KS 2585

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	624	Poz Class H	200 200	+6% gel+3% CaCl +3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			None		

Size	Setting depth	Packer set at			
None					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

RELEASED

Date: 6/30/82

FROM CONFIDENTIAL

INITIAL PRODUCTION

Date of first production None	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Ladd Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole			
Well No. 1	Lease Name Rooney	Logs run: DIL CNL-FDC-GR BHC-GR			
S <u>2</u> T <u>30</u> R <u>25</u> EX W					
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.			
FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Lansing LS-CRM, WH, TN, GY, F-MXC VCHKIP, VSUCIP, P SP LT BRN STN, FR FLOUR, SL CUT, SL VUG POR DST #1 4,662-4,709 TO-15 MIN, WEAK BLOW INC. TO GOOD BLOW SI-30 MIN TO-60 MIN, WEAK BLOW INC TO STRONG BLOW SI-120 MIN. IHP-2,256 FHP 2,256 IFP-49-147 FFP-180-344 ISIP-1,473 FSIP-1,473 REC. 240' MUDDY SALTWATER 475' SALTWATER BHT-110° Well was P & A'd. Plugged at 652' w/50 sx Class H 40' w/10 sx Class H to surface.		4672	4704	Stone Corral Cimarron Anhydrite Wellington Group Wellington Salt Hollenberger Herrington Upper Krider Lower Krider Winfield Upper Ft. Riley Lower Ft. Riley Florence Wreford Council Grove Cottonwood Limestone Neva Wabaunsee Topeka Heebner Toronto Lansing Kansas City Marmaton Cherokee Miss St. Genevieve Miss St. Louis	1502 1604 2048 2118 2639 2678 2716 2758 2814 2868 2902 2950 3034 3067 3160 3230 3696 3880 4368 4386 4482 4760 5023 5181 5276 5311
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.					
Date Received		Drilling Manager August 12, 1980			
		Date			