

TIGHT**CONFIDENTIAL****3-30-25** 7/21/83TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

(F) ☒ Letter requesting confidentiality attached.

(C) ☒ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 6033 EXPIRATION DATE 6-30-84

OPERATOR Murfin Drilling Company API NO. 15-025-20696

ADDRESS 250 N. Water, Suite 300 COUNTY Clark

Wichita, Kansas 67202 FIELD Norcan East

** CONTACT PERSON Ramona Gunn PROD. FORMATION Dry

PHONE (316)-267-3241 _____ Indicate if new pay.

PURCHASER _____ LEASE Fager

ADDRESS _____ WELL NO. 1-3

WELL LOCATION SW SE NE

DRILLING Murfin Drilling Company 990' Ft. from East Line and

CONTRACTOR 250 N. Water, Suite 300 330' Ft. from South Line of

ADDRESS Wichita, Kansas 67202 the NE (Qtr.) SEC 3 TWP 30S RGE 25 (F) (W)

PLUGGING Murfin Drilling Company WELL PLAT (Office Use Only)

CONTRACTOR 250 N. Water, Suite 300 KCC _____

ADDRESS Wichita, Kansas 67202 KGS ☒

TOTAL DEPTH 5450' PBTD _____ SWD/REP _____

SPUD DATE 7-7-83 DATE COMPLETED 7-21-83 PLG. _____

ELEV: GR 2573' DF _____ KB 2582' NGPA _____

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 1041' DV Tool Used? no

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

David L. Murfin, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

 State Geological Survey
WICHITA BRANCH

HEAT			
RELEASED			
AUG 1 1984			
Date: FROM CONFIDENTIAL			

AUG 1 1983

Side TWO

OPERATOR Murfin Drilling Co. LEASE NAME Fager SEC 3 TWP 30S RGE 25W (1)
WELL NO 1-3 (W)

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run. ☒ Check if samples sent Geological Survey. DST #1 5276-5366'/30-60-60-60 Rec 30' Mud, no shows HP: 2540-2540# FP: 14/14-20/20# SIP: 28-20# Surface Soil Red Bed Sand & Red Beds Shale Lime & Shale Lime RTD	0 510' 1041' 1160' 2340' 4984'	510' 1041' 1160' 2340' 4984' 5450'	Electric Log Tops Heebner Toronto Lansing Stark Marmaton Cherokee Morrow Shale Morrow Sand Mississippi	4367' (-1785) 4392' (-1810) 4488' (-1906) 4892' (-2310) 5026' (-2444) 5150' (-2568) 5260' (-2678) 5286' (-2704) 5295' (-2713)

~~TIGHT~~

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc.							
CASING RECORD (New) or (Used)							
Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Case	12¼"	8 5/8"	24#	1041'	Howco Lite Class H	350 200	3% CC 3% CC
LINER RECORD				PERFORATION RECORD			
Top, ft.	Bottom, ft.	Sacks cement		Shots per ft.	Size & type	Depth interval	
TUBING RECORD							
Size	Setting depth	Packer set at					