

11811

SIDE TWO

Operator Name Murfin Drilling Company Lease Name..... Goeller Well #..... 1-4

Sec..... 4 Twp..... 30S Rge..... 25 East West County..... Clark

WELL LOG

TIGHT

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
Samples Sent to Geological Survey Yes No
Cores Taken Yes No

Formation Description
 Log Sample

DST #1: 5300-5335'/30-45-60-90. Rec 950' s1 GO.
HP: 2597-2565#. SIP: 800-789#. FP: 165-187/209-280#. BHT: 116°.

Table with 3 columns: Name, Top, Bottom. Rows include Heebner, Toronto, Lansing, Stark, B/KC, Marmaton, Cherokee, Morrow Sand, Mississippi.

PRODUCTION CASING REPORT: Set 5 1/2" - 15.5# casing at 5449' cemented w/25 sx. Class A w/10% salt, 3/4% CFR-2 + 80 sx. 50-50 Pozmix w/10% salt, 3/4% CFR-2, 6#/sx. gilsonite + 60 sx. 50-50 Pozmix w/same + 1/2 gal. latex, 2% CC.

CASING RECORD, PERFORATION RECORD, TUBING RECORD, and production data sections. Includes details on casing size, weight, setting depth, and perforation intervals.