

KANSAS



IMPORTANT
Kans. Geo. Survey request
samples on this well.

State Geological Survey
WICHITA BRANCH
S. 8 T. 30 R. 25 E. W

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 - 025 - 20391
County Number

Loc. _____
County Clark

Operator
Ladd Petroleum Corporation

Address
830 Denver Club Bldg., Denver, CO 80202


Well No. 1-8 Lease Name Cannon

Footage Location
2310 feet from (N) line 1980 feet from (E) (W) line

Principal Contractor Rains & Williamson Geologist

Spud Date 8/20/80 Date Completed 9/7/80 Total Depth 5450' P.B.T.D. 5400' (est)

Directional Deviation Oil and/or Gas Purchaser



640 Acres
N
Locate well correctly
Elev.: Gr. 2573'
DF _____ KB 2582' (est)

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface		8-5/8	24	37 jts.	35/65 Poz, 6% gel, 3% CaCl	275	+ 10#/sk Kolite & 1/4#/sk D-29
				tailed in w/	Class "H"	200	2% CaCl
production		5 1/2	14	5448'	50/50 Poz + 2% gel	200	18% salt + .75% TIC
				followed by	RFC	150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		5281-86'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"		5198'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gal 7 1/2% HCl spearhead acid	5281-86'

RELEASED
Date: 10 AUG 1982
FROM CONFIDENTIAL

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
9/10/80	flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	150 bbls.	143 MCF	---	953 CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval(s)
vented	Morrow SS (5281-86')

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Ladd Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1-8	Lease Name Cannon	oil
S 8 T 30 R 25 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Morrow SS	5264'			
Mississippian	5291'			
Marmaton	5004'			
Kansas City	4747'			
Hebner Shale	4367'			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Michael J. Wendling</i>
	Signature
	Production Engineer
	Title
	9/26/80
	Date