

KANSAS DRILLERS LOG

API No. 15 — 025 — 20374
County Number

Operator
Ladd Petroleum Corporation

Address
830 Denver Club Bldg., Denver, CO 80202

Well No. 1-17 Lease Name Johnson (Wildcat)

Footage Location
1980 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor Rains & Williamson Geologist

Spud Date 9/4/80 Total Depth 5500' P.B.T.D. 5250'


Date Completed 9/30/80 Oil Purchaser

17 T. 30 R. 25 F. W

Loc. C NW SW

Clark

640 Acres
N



Locate well correctly

Elev.: Gr. 2569'

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12½"	8-5/8"	24#	677'	250 65/35 Poz 200 Cl "H"	450	3% CaCl
production	7-7/8"	5½"	14#	5342'	200 50/50 Poz 225 12-ORFC	975	
					550 50/50 Poz		

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
					5038-5040'
					5045-49'
					5052-56'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/2500 gal 28% HCl & 7500 gals 28% HCl	5038-49'

RELEASED

Date: 18 AUG 1982

FROM CONFIDENTIAL

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
10/4/80	Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	81 bbls.	trace MCF	2 bbls.	— CFPB

Disposition of gas (vented, used on lease or sold)
vented

Producing interval(s)
Marmaton lime

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

ator

Ladd Petroleum Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:Well No.
1-17Lease Name
Johnson (Wildcat)

Pl

S 17 T 30 R 25 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Stone Corral	1476'			
Wellington Salt	2024'	2507'		
Wabaunsee				
Winfield	2771			
Heebner	4354			
Lansing	4461			
Kansas City	4738			
Marmaton	4998			
Cherokee	5182			
Morrow Sand	5270			
Mississippian	5294			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Michael J. Wendling
Signature

Title

Date