

PI

18-30-25

AFFIDAVIT OF COMPLETION FORM

State Geological Survey  
WICHITA BRANCH

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR TXO PRODUCTION CORP.

API NO. 15-025-20,536

ADDRESS 200 W. Douglas, Suite 300  
Wichita, Kansas

COUNTY Clark

FIELD Minneola

\*\*CONTACT PERSON Harold R. Trapp

PROD. FORMATION Dry

PHONE 316-265-9441

LEASE Church

PURCHASER N/A

WELL NO. #2

ADDRESS \_\_\_\_\_

WELL LOCATION \_\_\_\_\_

DRILLING H-30 Drilling, Inc.

660 Ft. from East Line and

CONTRACTOR \_\_\_\_\_


660 Ft. from North Line of

ADDRESS 251 N. Water

the 18 SEC. 30S TWP. 25 RGE.

Wichita, KS

PLUGGING Same



WELL PLAT

CONTRACTOR \_\_\_\_\_

KCC \_\_\_\_\_

ADDRESS \_\_\_\_\_

KGS

TOTAL DEPTH 5380' PBDT N/A

MISC \_\_\_\_\_

SPUD DATE 11-1-81 DATE COMPLETED 11-15-81

(Office Use)

ELEV: GR 2573' DF \_\_\_\_\_ KB 2586'

DRILLED WITH ~~(XXXXX)~~ (ROTARY) ~~(XXXX)~~ TOOLS (New) / ~~(Used)~~ casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8"	24#	647'		600	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	N/A	N/A	N/A

TUBING RECORD

Setting depth	Packer set at

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1981

28-02-81

Name of lowest fresh water producing stratum Unknown Depth N/A

Estimated height of cement behind Surface Pipe N/A

DV USED? N/A

18-30-25W

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
<u>LOG TOPS</u>				
Altamont	5060	-2474		
Pawnee	5108	-2522		
Ft. Scott	5140	-2554		
Cherokee	5155	-2569		
Morrow	5274	-2688		
Mississippi	5332	-2746		
RTD	3380			
LTD	3381			
Ran O.H. Logs				
<u>DST #1, 5290-5335' (Morrow SD.) w/results as follows:</u>				
IFP/30"=76-76 psig,				
ISIP/60"=96 psig.				
FFP/10"=76-76 psig, no blow, pulled tools				
Rec.: 20' mud. CTCH				

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS, \_\_\_\_\_

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS District Geologist (FOR) ~~XXX~~ TXO Production Corp.

OPERATOR OF THE Church LEASE, AND IS DULY AUTHORIZED TO MAKE

ch PI

Name of lowest fresh water producing stratum \_\_\_\_\_ Depth \_\_\_\_\_

Estimated height of cement behind Surface Pipe circulated .

DV USED? \_\_\_\_\_

WELL LOG

18-30-25W

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Sand and Red Bed				330'
Red Bed and Shale				659'
Shale				765'
Red Bed and Shale				1828'
Shale and Lime				2050'
Lime and Shale				3140'
Shale and Lime				3306'
Lime and Shale				4095'
Shale and Lime				4255'
Lime and Shale				4415'
Shale and Lime				4458'
Lime and Shale				5380'
Rotary Total Depth				5380'

A F F I D A V I T

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_ SS, \_\_\_\_\_

\_\_\_\_\_ OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS \_\_\_\_\_ (FOR)(OF) \_\_\_\_\_

\_\_\_\_\_ PATOR OF THE \_\_\_\_\_ LEASE, AND IS DULY AUTHORIZED TO MAKE