

FORMATION

TOPS

25

Sec.

30

Twp.

34W

Rge.

SE SE NW

Location

Haskell

County

Kansas

State

2956

Elevation

Cities Service Oil

Company

1

Well No.

Schnellbacher

Farm

U.K. 2600-16

L.K. 2622-55

Winf. 2668-94

U.F.R. 2717

100 S Line

Feet from of NW/4


100 E Line

Feet from

CASING

8 5/8" 640 (300)

5 1/2" 2769 (800)



Producing Formation

T. D.

2770

I. P.

14.000M

Date

Sp. 6-27-49.

R.T.D. 2770. RUST C.O. to 2754. Perf. 140 holes

2718-46, 537Mcf. A/2000 gals., 24 hr. B.D. 2.340M.

Perf. 110 holes 2670-92. Perf. 150 holes 2624-54.

Perf. 70 holes 2602-16. A/2000 gals. 2602-54.

A/1000 gals. 2670-92, 24 hr. B.D. 3.040M. A/10,000

gals. 2602-54. A/4500 gals. 2670-92. A/6000 gals.

2718-46, 24 hr. B.D. 4.090M. 48 hr. B.D. 4.090M.

A/9000 gals. 5% all perms., 24 hr. B.D. 4.090M.

I.P. 14.000M R.P. 403.7#

AUG 2 '49

¢