

State Geological Survey
WICHITA, BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geol. Surv. request
samples on this well.


API No. 15 — 119 — 20,252
County Number

S. 34 T. 30 R. 27 E W

Loc. C SE

County Meade

640 Acres
N



Locate well correctly

Elev.: Gr. 2461'

DF 2470' KB 2472'

Operator Price Exploration Co.		
Address 814 Mayo Bldg., Tulsa, Oklahoma 74103		
Well No. #1	Lease Name Copenhaver	
Footage Location 1370' feet from (N) (S) line 1320' feet from (E) (W) line		
Principal Contractor Rine Drilling Company	Geologist Michael D. Spain	
Spud Date 2-14-77	Total Depth 5420'	P.B.T.D.
Date Completed 2-27-77	Oil Purchaser	

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Pipe		8-5/8"	24#	1390'	HOWCO Light HOWCO Class	550 H 150	2% cc 1/4# Flocele 3% cc 1/4# Flocele

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Dry and Abandoned		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Price Exploration Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Copenhaver	Dry Hole
S 34 T 30 R 27 X W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0'	456'	Electric Log	Tops:
Red Bed & Sand	456'	893'		
Red Bed, Sand & Anhydrite	893'	1380'	Herrington	2582
Red Bed	1380'	1395'	Krider	2608
Red Bed & Shale	1395'	2586'	Winfield	2650
Lime & Shale	2586'	5420'	Towanda	2712
			Ft. Riley	2774
			Florence	2823
			Wreford	2873
DST #1 5195'-5255', 30-60-45-90,			Council Grove	2983
IHP 2499			Cottonwood	3120
IFP 52-65			Neva	3148
ISIP 131			Wabaunsee	3400
FFP 65-65			Howard	3654
FSIP 92			Topeka	3761
FHP 2499			Heumater	4196
BHT 122°			Heebner	4222
Rec 30' DM			Toronto	4244
			Lansing	4366
			Kansas City	4472
			Swope	4718
			B/KC	4838
			Marmaton	4876
			Lenapah	4890
			Altamont	4924
			Pawnee	4980
			Ft. Scott	5011
			Cherokee	5022
			Basal Atoka	5170
			Morrow Shale	5188
			Morrow Sd Zn	5196
			Chester	5239
			Chester Lime	5254
			St. Genevieve	5302
			RTD	5420

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Richard E. Price
Owner

Title

March 8, 1977

Date