

9-247W Map No. K-83  
OPER SATURN OIL & GAS CO., INC. -  
Cheyenne, Wyoming  
WELL #1 TOWLER "A"  
INTR Moran Brothers  
FIELD Panoma (CG Gas)  
I.P. SI Gas Well, Ga 3,258,000 Cfgpd (5 hr BD)  
from CG 2703-2812



S-T-R 27-30S-37W  
SPOT App C NW ✓  
CG GRANT (Ks)  
ELEV 2998 GR

(GR Log)

|      |            |
|------|------------|
| Winf | 2448 / 550 |
| U/FR | 2522 / 476 |
| L/FR | 2577 / 421 |
| CG   | 2686 / 312 |
| Adm  | 2880 / 118 |
| LTD  | 2989 / 9   |
| RTD  | 2990 / 8   |

No DST's, RTD 2990, Ran Log, 5" @2986 w/200 sx.,  
Pf 8/2710-12 (CG), no sho nat, 250A, § ld, § dry, no  
shos/2½ hrs, Pf 16/2788-96, 16/2768-76, 12/2742-48, 20/  
2718-28, 8/2703-07 (CG), § no sho nat, 3000A & 100 ball  
sealers, Ga 540,000 Cfgpd & 60 gal wtr/PH/3 hrs,  
Frac 80,000 gal wtr & 60,000# sd, Ga 3,258,000 Cfgpd  
& ld, 1½" tbg @2706, - 5 hr BD, Ga 3,258,000 CFGPD, CG  
2703-2812 - SI Gas Well - COMPLETED on 9-21-65

*Liberal Electric Log Gaps*

2998 GR

Data Inc

*Winfield*  
*C. G.*

2454 + 544

2702 + 296 & 3,258 MCF

TD

2990

MISCEL DATA

GEOL No Geol on test ELEV 3005 KB SPUD DATE 8-24-65  
FTG 3002 DF DRLG COMP  
SUPPT 8-16-65  
CSG 8" @662 w/400 sx. 5" @2986 w/200 sx. COMP by 9-23-65

L-53000 DF