


12-336W Map No. K-83
OPER SATURN OIL & GAS CO.

WELL #1 BROLLIER "B"

TR Moran Drlg.

FIELD Panoma (C Gr Gas) Area

I.P. Ga 3,544,000 Cfgpd (wet) from C Gr 2791-2930



S-T-R 29-30S-37W

SPOT App C NW

CO GRANT (Ks)

ELEV 3121 KB

(KB Log)

U/FR 2604 f 517

L/FR 2659 f 462

FF 2724 f 397

C Gr 2770 f 351

LTD 3010 f 111

RTD 3010 f 111

- note oper change - Was Anadarko - Is Saturn
No DST's, RTD 3010, Log, 5½" @3009 w/200 sx.

PF 16/2922-30 (C Gr), 500A, Ga 987,000 Cfgpd/19½ hrs,
14/2872-78, 9/2803-57, 9/2838-40, 9/2822-24, 9/2803-05,
14/2791-97 (C Gr), Pkr @2904, 3000A, Ga 198,000 Cfgpd &
10 GWPH/20 hrs - Frac 100,000 GW x 60,000# sd, § & flo ld,
Ga 2,026,000 Cfgpd/4 hrs (wet), 1½" tbg @2802,
3,080,000 Cfgpd (wet), SICP 345#/22 hrs, Ga 3,103,000
Cfgpd/3 hrs - CO 2950, Ga 3,544,000 Cfgpd (wet) from
C Gr 2791-2930 - COMPLETED (12-23-65)

Liberal E-log Yape

3107 GR

Wunfield 2534 + 573

Council Grove 2788 + 319 & 3,544 MCF

TD 3010

Data Inc

MISCEL DATA

GEOL _____ ELEV 3119 DF

FTG 1250' FNL x 1390' FWL 3107 GR

SUPPT Anadarko Prod - Interest

CSG 8" @647 w/400 sx. 5½" @3009 w/200 sx.

SPUD DATE 11-15-65

DRLG COMP _____

FR by DATA 11-17-65

COMP by " 12-29-65