

Flow Time	1st 30 Min.	2nd 30 Min.	Date	12-21-61	Ticket Number	314994
Closed In Press. Time	1st 20 Min.	2nd 20 Min.	Kind of Job	Open Hole	Halliburton District	Winfield
Pressure Readings	Field	Office Corrected	Tester	Bob O'Neal	Witness	Geo. R. McNeish
Depth Top Gauge	4273 Ft.	No Blanked Off	Drilling Contractor	Jones & Gebert		
BT. P.R.D. No.	291	12 Hour Clock	Elevation	1344' DF	Top Packer	-
Initial Hydro Mud Pressure		2175	Total Depth	4285'	Bottom Packer	4279'
Initial Closed in Pres.		21	Interval Tested	4279-4285'	Formation Tested	Simpson
Initial Flow Pres.	1 14	2 15	Casing or Hole Size	7 7/8"	Casing Perfs. Top Bot.	-
Final Flow Pres.	1 14	2 15	Surface Choke	1/4"	Bottom Choke	5/8"
Final Closed in Pres.		15	Size & Kind Drill Pipe	4 1/2" FH	Drill Collars Above Tester	-
Final Hydro Mud Pressure		2164	Mud Weight	9.7	Mud Viscosity	40
Depth Cen. Gauge		Blanked Off	Temperature	136 °F Est. °F Actual	Anchor Size & Length	ID 2 3/8 X 6' OD 4 1/2
BT. P.R.D. No.		Hour Clock	Depths Mea. From	KB	Depth of Tester Valve	4270' Ft.
Initial Hydro Mud Pres.			Cushion		Depth Back Pres. Valve	
Initial Closed in Pres.			Recovered	3 Feet of	drlg mud	
Initial Flow Pres.	1		Recovered	Feet of		
Final Flow Pres.	1		Recovered	Feet of		
Final Closed in Pres.			Recovered	Feet of		
Final Hydro Mud Pres.			Oil A.P.I. Gravity		Water Spec. Gravity	
Depth Bot. Gauge	4281 Ft.	Blanked Off	Gas Gravity		Surface Pressure	psi
BT. P.R.D. No.	2120	Hour Clock	Tool Opened	8:05 PM	A.M. P.M. Tool Closed	9:25 PM A.M. P.M.
Initial Hydro Mud Pres.			Remarks	Tool open at 8:05 PM with a very weak		
Initial Closed in Pres.				blow. Closed at 8:35 PM. Reopen at 8:55 PM		
Initial Flow Pres.	1			with no blow. Closed at 9:25 PM.		
Final Flow Pres.	1			No special reading adaptable.		
Final Closed in Pres.						
Final Hydro Mud Pres.						

LEEDY

Lease Name

1

Well No.

2

Test No.

GRALAPP & EVERLY


Lease Owner/Company Name

KANSAS


Owner's District

FORMATION TEST DATA

↑ PRESSURE ↓



← TIME →



A—Initial Mud Weight
B—Initial Flow
C—Final Flow
D—Closed in Pressure
E—Final Mud Weight

HALLIBURTON FORM 1260—LITTLE'S 5742-28 10/50

EACH HORIZONTAL LINE EQUAL TO 1000 P.S.I.