

Need Draper log

90322

A-6-233

MAP NO. 83 ✓

ELEV. 2979GL, 2987DF

STATE Kans. COUNTY Grant SEC. 3

Twp 30S Rge 35W

OPERATOR United Producing Co., Inc.-Liberal

LOC. C SE NE

WELL NO. 2 FARM NAME McCabe Unit

FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_

POOL Wildcat (PD 5700)

FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_

FR. 4-24-61 SPUD 5-7-61 COMP. 6-27-61

CONT./GEOL. \_\_\_\_\_

COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a Marmaton	4699-4701	8	250Ac
b Morrow <u>lm</u>	5312-17	12	None
c _____	_____	_____	_____
d _____	_____	_____	_____


d I. P. OIL/DIST. S/120 BOED GAS \_\_\_\_\_ M.C.F.P.D. \_\_\_\_\_ CHK. Swab HRS. 24

b " S/190 BOED " " " " Swab " 24

c " " " " " " " "

d \_\_\_\_\_

D & A ( )

SIP# \_\_\_\_\_ FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_

GOR. \_\_\_\_\_ GR. 360(a) ± 38.50(b) BTD 5329 TD 5882

CASING - CEMENT RECORD

SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
8-5/8"	1748	750			
5-1/2"	5430	250			

OPERATOR United Producing Co. WELL NO. #2 McCabe Unit

ELEV. 2987 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Council Grove	2784	4195
			Wabaunsee	3198	
			Toronto	3958	
			Lansing "A"	4043	
			Kansas City "A"	4518	
			Marmaton Pay	4700	1721
			Morrow	5234	2255
			Morrow Lime	5280	2301
			Chester Sand	5466-76	2487
			Chester Sand	5512-32	2533
			Mera	5532	
			St Louis	5630	2651

Spud 5-7-61. 8-5/8" @ 1748 w/750 sx.

DST #1 (CG) 2800-2900, op 1 hr, GTS 40 mins, TSTM, Rc 180' GCM, ISIP 464/30 mins, FP 42-84, FSIP 464/30 mins.

DST #2 (CG) 3104-17, op 1 hr, Rc 20' M, ISIP 275/30 mins, FP 10-10, FSIP 135/30 mins.

DST #3 (Lans) 4038-70, op 1 hr, Rc 1260' MSW, ISIP 1096/30 mins, FP 84-590, FSIP 1053/30 mins.

- DST #4 (KC "A") 4519-47, op 1 hr, rec 180' SGCXW, ISIP 1320/20,  
 FP 30-80, FSIP 1240/30:  
 DST #5 (KC "B") 4571-4625, op 1 hr, rec 15' Mud, ISIP 1524/30,  
 FP 102-102, FSIP 959/30:  
 DST #6 (Marm) 4697-4716, op 1 hr, GTS 15 mins, TSTM, rec 471' oil  
 + 130' HO&GCM + 50' O&GCXW, ISIP 1397/30, FP 63-189, FSIP  
 1290/30:  
 DST #7 (Mor) 5466-82, op 1 hr, rec 2' mud/NS, ISIP 947/30, FP  
 13-15, FSIP 441/30:  
 DST #8 (Chest) 5512-46, op 1 hr, rec 1550' GCXW + 5' M, ISIP 1503/  
 /30, FP 217-712, FSIP 1398/30:  
 RTD 5880, ran logs to 5882.  
 DST #9 (Mor) 5314-66 (SP), op 1 hr, rec 190' SOCM + 1120' oil +  
 180' O&GCM, ISIP 1595/30, FP 325-650, FSIP 870/30:  
5½" @ 5430/250 sx. MICT; P 24/5341-47, 64/5354-70, A/4000,  
 swb ½ GOPH, frac/10,000 ac x sd/10,000, swb pt ld w/NS, set  
 BP @ 5331; P 12/5312-17, swb 127 BO/16 hrs, set BP @ 5288:  
 P 8/4699-4701, bld 1 GOPH/NT, A/250, swb ld, swb 16 BFPH (65%  
 oil + 35% wtr), CO 5329.  
 From 4699-4701, swb 120 BOPD from 5312-17 swb 190 BOPD, 2"  
 tbg & pkr @ 5300, dual string 4600.  
 IP swb 120 BOPD, G. 36° from Marmaton 4699-4701.  
 IP swb 190 BOPD, G. 38.5° from Morrow 5312-17.  
 Dual Completion. 6/27/61.

LIBERAL ELECTRIC LOG TOPS

2990 KB

Winfield 2552 (+348)  
 Council Grove 2806 (+184) tst 180' GCM, gas/TSTM  
 Heebner 3934 (-944)  
 Toronto 3952 (-962)  
 Lansing 4042 (-1052) tst XW in "A" & "D" Zones; Mud in "E" & "E-1"  
 Marmaton 4654 (-1664)  
 Pay Zone 4700 (-1710) \$ 120 BOPD ¢  
 Morrow 5228 (-2238)  
 Lm 5280 (-2290) ¢ swb 190 BOPD  
 "S-3" 5466 (-2476) 2/10; tst mud  
 Chester 5476 (-2486)  
 Sand 5512 (-2522) 20/20; tst GCXW  
 Ste. Gen 5556 (-2566)  
 St. Louis 5774 (-2784)  
 TD 5880