

6-62W +
 MAP NO. SEC. 30 TWP. 30S RGE. 33W
 STATE Kans COUNTY Haskell 50' No of - LOC. C NW SE
 OPERATOR Pan American Pet. Corp. FT. FROM LINE
 WELL NO. 1 FARM NAME Schnellbacker Gas Unit A FT. FROM LINE
 (Geol WC in Victory Pool) ELEV. 2951 GR. 2958 DF. 2961 KB
 3/20/62 SPUD. 3/19/62 COMP. 6/12/62

CONT. Big Chief Drlg. Tools /GEOL.

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD
 a. Lans 4121-26 A 20 5000 A

b. _____

c. _____

d. Cal Flo

a I. P. OIL/DIST. 198 B WTR. 0 GAS M.C.F.P.D. CHK. HRS. 24

b. " " " " " "

c. " " " " " "

d. _____

SIP# FI TP # FI CP# SIBHP

GOR. GR. 38° PBD 4140 TD 5563

SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.

8 5/8" 740 300

5 1/2" @ 5451 225

OPERATOR Pan American WELL NO. 1 Schnellbacker G.U ELEV. 2961 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums.					
Penn	3284	- 332	Chase	2588	+ 373
Tor	4002	-1041	CG	2876	- 85
Mo	4072		Penn	3400	- 439
Des M	4742		Mo	4091	-1130
Morr	5205		Lans	4117	-1156
Ches	5345		Des M	4770	-1809
RTD (St Lou)	5563	-2602	Morr	5311	-2350
			Ches	5360	-2399
			St. Gen	5409	-2448
			St. Lou	5524	-2563

RTD 5563. Sj Log:

WLT #1 (Chest) 5332, Op 1 hr., R 50 cc wtr., IBHP 50#/15"
 FBHP 50#/15".

5 1/2" @ 5451 w/225 sx. CO 5563. PB 5415, 8/5410-12 (St Gen)
 Swb dry, 500 A, Swb ld, no sho, 2000 A, Rec ld, Swb 2
 BFW/w sli sho gas/4 hrs, PB 5400, 12/5371-74 (Chest) 100
 Acid, Swb ld, no sho, Frac (11,000 GW x 8000# sd) Swb ld,
 No sho, PB 5310, 4/4593 1/2 (Lans) Swb ld, Swb 5 GO + 12

BWPH/NT. PB 4564. 8/4412-14 (Lans) swb dry, Nat. A/1000 (15%), swb ld, 229 BFW w/sho oil, gas TSTM, PB 4372.
8/4156-58 (Lans) A/1000 15%, flo 111 BO + 22 BW (ld) thru 24/64" ck, FCP 380#, G. 35.3°, flo 77 BO + 3 BW/6 hrs, Pkr 4138, 12/4121-24 (Lans) Flo 9 BOPH, est g 1,500 MCF/3 hrs, thru 18/64" ck, FCP 460#, Kill zone 4121-24: tbg into pkr @ 4138. flo 250 BO, SICP 960#, SITP 760#, kill w/ 100 BO, Circ 25 Sx. cem. 8/4158-60, (Lans) A/1000 (15%), swb ld, Swb 20 BF/12% oil/1 hr, Swb 130 BO + 65 BW/13 hrs, G. 35°, SQ/4158-60/50 sx, 4/4155-56 (Lans) Tbg w/pkr @ 4142, A/1000, Swb 11 BFW w/sli sho oil & gas, Swb 4 BO + 199 BFW/21 hrs. Swb 8 GO + 11 BWPH/8 hrs, SQ/4155-56 w/50 sx. CO 4140 PBTD, 8/4124-26 (Lans) A/1000, swb dry, 1000 acid + 3000 acid, Swb & flo 61 BNO/13 hrs, flo 5 BOPH, 18/64" ck, 1 hour, Sho gas, FCP 660#, SICP 760#/1 hour, flo 10 BO/7 hrs, State Pot: 6/5/62 (8 hr flo) Cal Flo 198 BOPD/NW. G/ 38°, Lansing 4121-26, PBTD 4150.

LIBERAL ELECTRIC LOG TOPS

2961 KB

Winfield 2658 (+303)
Heebner 4021 (-1060)
Toronto 4038 (-1077)
Lansing 4116 (-1155) COF 198 BOPD
"D" Zone 4590 (-1629)
Marmaton ~~4728 (-1767)~~ → 4770 - 1809 Amarillo
Morrow 5312 (-2351)
Sand 5353 (-2392) 0/7
"S-2" 5366 (-2405) 5/15 ; WLT 50 cc form wtr
Ste. Gen 5409 (-2448)
St. Louis 5528 (-2567)
TD 5563

3 Chest 5366 - 2405