

2-98W
MAP NO. K-84

ELEV. 2954DF 2957KB

STATE Kans. COUNTY Haskell SEC. 31 TWP. 30S RGE. 33W

OPERATOR Cities Service Pet. Co. LOC. C NW NE

WELL NO. 2 FARM NAME Schnellbacher "B" FT. FROM _____ LINE _____

FR. 12/20/61 SPUD 12/18/61 COMP. 2/13/62 FT. FROM _____ LINE _____

CONT./GEOL. Lohmann Johnson Drlg. Tools

NAME PRODUCING INTERVAL Lans FROM - TO 4135 PERF. W/HOLES notch TREATMENT RECORD 250A

b _____

c _____

d _____

d F1

d I. P. OIL/DIST. 214 BO WTR. NW GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. 5000-1 GR. 38.5° PBTD 4160 TD 4765

SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.

8-5/8" 648 300 _____

5 1/2" 4764 650 _____

OPERATOR Cities Service Pet. WELL NO. 2 Schnellbacher "B" ELEV. 2957 KB

SAMPLE TOPS DEPTH SUB SEA ELEC. TOPS DEPTH SUB SEA

KB Tops & Datums

Hb 4022 -1065

Tor 4042 -1085

RTD 4765 -1808 Lans 4110 -1153

Lans "B" 4568 -1611

DST #1 (Tor) 4042-60, Marm 4694 -1737

Op 1 hr., R 960' SW,

IFP 44#, FFP 255#, FBHP 962#/20"

DST #2 (Lans) 4106-20, Op 1 hr., GTS/3", Ga 892 Mcfgpd/10"

Ga 1360 Mcfgpd/60", R 90' HO&GCM, IFP 115#, FFP 160#,

FBHP 1090#/30"

DST #3 (Lans) 4122-35, Op 50", GTS/4", Ga 140 Mcfgpd/10"

TSTM/20", R 2340' oil + 270' HO&GCM, IFP 146#, FFP 516#

FBHP 1003#/20"

DST #4 (Lans) 4568-80, Op 50", GTS/22", TSTM, R 110' HG &

SOCM + 10' W, IFP 0#, FFP 9#, FBHP 1022#/30"

RTD 4765, SJ Log, 5 1/2" @ 4764 w/650 sx, CO 4710, 64/4572-80

(Lans) Swb 43 GW, tr oil/13 hrs, 250 MA, Swb 1-2/3 BO +

13-1/3 BW/5 hrs, PB 4439, 24/4416-22 (Lans) 250A (15%)

Swb 9 1/2 BO + 88 1/2 BW/NT, Sq 4416-22, 100 sx, CO 4415,

Notch @ 4396 (Lans) bail 6 GW/5 hrs, 250 MA, swb 53 1/3 GW
+ tr oil & SG/12 hrs, PB 4160, Notch 4135A (Lans) NS, Nat,
A/250, flo 215 BO, 2% BS&W, g 857 MCF/21 hrs, 2" tbg
4158, flo 214 BO/21 hrs, GOR 5000:1, Grav 38.5° from Lansing
Notch @ 4135.

LIBERAL ELECTRIC LOG TOPS

2957 KB

Heebner 4022 (-1065)

Toronto 4042 (-1085)

Lansing 4110 (-1153) ϕ flo 214 BO/21 hrs.

"D" Zone 4568 (-1611)

Marmaton ~~4694 (-1737)~~ \rightarrow 4735-1778 Amarillo

TD 4765