


15-081-21640

15-30s-32w



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Presco Western**

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

15/30S/32W

Daiden Farms #3

Start Date: 2006.01.28 @ 23:48:31

End Date: 2006.01.29 @ 17:56:14

Job Ticket #: 22373

DST #: 1

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Presco Western
5480 Valmont Ste 350
Boulder CO 80301
ATTN: Mike Dodge

Daiden Farms #3
15/30S/32W
Job Ticket: 22373 **DST#: 1**
Test Start: 2006.01.28 @ 23:48:31

GENERAL INFORMATION:

Formation: **Lansing**
Deviated: **No** Whipstock: ft (KB)
Time Tool Opened: 07:36:59
Time Test Ended: 17:56:14

Test Type: Conventional Straddle
Tester: Dustin Rash
Unit No: 20

Interval: **4504.00 ft (KB) To 4528.00 ft (KB) (TVD)**
Total Depth: **4570.00 ft (KB) (TVD)**
Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2082.00 ft (KB)**
2077.00 ft (CF)
KB to GR/CF: **5.00 ft**


Serial #: 6770

Inside

Press@RunDepth: **329.54 psig @ 4506.00 ft (KB)**
Start Date: **2006.01.28** End Date: **2006.01.29**
Start Time: **23:48:31** End Time: **17:56:14**

Capacity: **7000.00 psig**
Last Calib.: **1899.12.30**
Time On Btm: **2006.01.29 @ 06:48:29**
Time Off Btm: **2006.01.29 @ 12:35:44**

TEST COMMENT: IF- Fair building blow . Built to 13 inches.
IS- No blow back.
FF- Fair building blow . Built to BOB in 53 min.
FSI- No blow back.



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2411.69	113.59	Initial Hydro-static
49	64.30	115.08	Open To Flow (1)
78	156.27	121.44	Shut-In(1)
137	1338.96	121.25	End Shut-In(1)
138	199.43	120.78	Open To Flow (2)
197	329.54	124.32	Shut-In(2)
338	1345.17	123.17	End Shut-In(2)
348	2159.66	121.35	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
283.00	85% Water 15% Mud	1.39
283.00	90% Water 10% Mud	1.39
30.00	100% Mud	0.15

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Presco Western

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

Daiden Farms #3

15/30S/32W

Job Ticket: 22373

DST#: 1

Test Start: 2006.01.28 @ 23:48:31

Tool Information

Drill Pipe:	Length: 3883.00 ft	Diameter: 3.80 inches	Volume: 54.47 bbl	Tool Weight: 2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 22000.00 lb
Drill Collar:	Length: 596.00 ft	Diameter: 2.25 inches	Volume: 2.93 bbl	Weight to Pull Loose: 35000.00 lb
			Total Volume: 57.40 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	5.00 ft			String Weight: Initial 68000.00 lb
Depth to Top Packer:	4504.00 ft			Final 76000.00 lb
Depth to Bottom Packer:	4524.00 ft			
Interval between Packers:	20.00 ft			
Tool Length:	96.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4475.00	
Shut In Tool	5.00			4480.00	
Sampler	3.00			4483.00	
Hydraulic tool	5.00			4488.00	
Jars	5.00			4493.00	
Safety Joint	2.00			4495.00	
Packer	5.00			4500.00	30.00 Bottom Of Top Packer
Packer	4.00			4504.00	
Stubb	1.00			4505.00	
Perforations	1.00			4506.00	
Recorder	0.00	6770	Inside	4506.00	
Perforations	17.00			4523.00	
Recorder	0.00	13761	Inside	4523.00	
Blank Off Sub	1.00			4524.00	20.00 Tool Interval
Packer	4.00			4528.00	
Stubb	1.00			4529.00	
Change Over Sub	1.00			4530.00	
Drill Pipe	31.00			4561.00	
Change Over Sub	1.00			4562.00	
Perforations	5.00			4567.00	
Recorder	0.00	10993	Outside	4567.00	
Bullnose	3.00			4570.00	46.00 Bottom Packers & Anchor
Total Tool Length:		96.00			



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Presco Western

Daiden Farms #3

5480 Valmont Ste 350
Boulder CO 80301

15/30S/32W

Job Ticket: 22373

DST#: 1

ATTN: Mike Dodge

Test Start: 2006.01.28 @ 23:48:31

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity: 105000 ppm

Viscosity: 35.00 sec/qt

Cushion Volume:

bbl

Water Loss: 11.94 in³

Gas Cushion Type:

Resistivity: 0.09 ohm.m

Gas Cushion Pressure:

psig

Salinity: 3200.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
283.00	85% Water 15% Mud	1.392
283.00	90% Water 10% Mud	1.392
30.00	100% Mud	0.148

Total Length: 596.00 ft

Total Volume: 2.932 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Serial #: 6770


Inside

Presco Western

15/30S/32W

DST Test Number: 1

Pressure vs. Time






DRILL STEM TEST REPORT

Prepared for

Presco Western. LLC
5480 Valmont Ste 350
Boulder CO 80301

Daiden Farms #3
15-30S-32W
Haskell Co Kansas

Trilobite Testing, Inc
PO Box 362 - Hays, Kansas - 67601
ph: 785-625-4778 fax: 785-625-5620
e-mail: trilobite@eaglecom.net



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Presco Western, LLC
5480 Valmont Ste 350
Boulder CO 80301

Well name#:	Daiden Farms #3	Date:
Location#:	15-30S-32W Haskell Co Kansas	Ticket #:
		DST#

General Informaion:

Formation:	KC 'A'	Test Type:	Conventional	BHT:
Interval:	4688-4718	Tester:	Dustin Rash	OIL API:
Total Depth:	4770	Elevation:	2082 ft(KB)	H2O Salinity:
Hole Diameter:	7 7/8"		2077 ft(CF)	

Start Data:	Tool Weight:	2000	Mud Type:	Chemical
Start Time:	Weight Set on Packers:	20000	Mud Weight:	
Time tool opened:	Weight to Pull Loose:	35000	Viscosity:	
Time Off Btm:	Initial String Weight:	77000	Water Loss:	
End Date:	Final String Weight:	81000	Resistivity;	
End Time:	Drill Pipe Length:		Salinity:	
	Drill Collar Length:	596		
	Wt. Pipe Length:			

Test Comment:

IF: Weak surface blow.
ISI: No blow back.
FF: No blow.
FSI: No blow back.


Lost Electronic Recorder Down Hole.

Recovery

Length(ft): 114 Watery mud 20% W 80%M

Gas Volume Report

Recorder #:	10993	Min:	Ins. Of water	Orifice	MCF/D
Pressure Summary:	Time:(min)		PSIG	size	
Initial Hydro-static:	2291				
Open to Flow (1):	56 30				
Shut-in (1):	56 60				
End Shut-in (1):	1341				
Open to Flow (2):	79 60				
Shut-in (2):	90 120				
End Shut-in (2):	1331				
Final Hydro-static:	2154				



TRILOBITE TESTING INC.

P.O. Box 362 • Hays, Kansas 67601

No 22374

Test Ticket

Well Name & No. Darden Farms #3 Test No. 2 Date 1-30-06
 Company Presco Western Zone Tested KC 'A'
 Address _____ Elevation 2082 KB 2077 GL
 Co. Rep / Geo. Mike Dodge Cont. _____ Est. Ft. of Pay _____ Por. _____ %
 Location: Sec. 15 Twp. 30S Rge. 32W Co. Haskell State KS
 No. of Copies _____ Distribution Sheet (Y, N) _____ Turnkey (Y, N) _____ Evaluation (Y, N) _____

Interval Tested 4688-4718 Initial Str Wt./Lbs. 77K Unseated Str Wt./Lbs. 81K
 Anchor Length 80' Wt. Set Lbs. 20K Wt. Pulled Loose/Lbs. 35K
 Top Packer Depth 4683 Tool Weight 2K
 Bottom Packer Depth 4688 Hole Size 7 7/8" Rubber Size 6 3/4"
 Total Depth 4770 Wt. Pipe Run N/A Drill Collar Run 596
 Mud Wt. 8.9 LCM 03# Vis. 41 WL 12.4 Drill Pipe Size 4.5X14 Ft. Run _____
 Blow Description IF- Weak surface blow
IS- No blow back
FE- No blow
FBI- No blow back

lost electronic recorder in hole

Recovery - Total Feet 114 GIP _____ Ft. in DC _____ Ft. in DP _____
 Rec. 114 Feet of watery mud %gas _____ %oil 20 %water 80 %mud
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud

BHT _____ °F Gravity _____ °API D @ _____ °F Corrected Gravity _____ °API
 RW 1331 @ 73 °F Chlorides 25,000 ppm Recovery _____ Chlorides 9700 ppm System

	AK-1	Alpine	PSI	Recorder No.	Test	
(A) Initial Hydrostatic Mud	<u>2291</u>			<u>6770</u>	<u>Saddle</u>	<u>1100</u>
(B) First Initial Flow Pressure	<u>56</u>			(depth)	Jars <u>✓</u>	<u>200</u>
(C) First Final Flow Pressure	<u>56</u>			Recorder No. <u>10993</u>	Safety Jt. <u>✓</u>	<u>50</u>
(D) Initial Shut-In Pressure	<u>1341</u>			(depth)	Circ Sub <u>✓</u> <u>NIC</u>	
(E) Second Initial Flow Pressure	<u>79</u>			Recorder No. <u>13761</u>	Sampler <u>✓</u>	<u>200</u>
(F) Second Final Flow Pressure	<u>90</u>			(depth)	Straddle <u>✓</u>	<u>250</u>
(G) Final Shut-In Pressure	<u>1331</u>			Initial Opening <u>30</u>	Ext. Packer _____	
(Q) Final Hydrostatic Mud	<u>2154</u>			Initial Shut-In <u>60</u>	Shale Packer _____	
				Final Flow <u>60</u>	Ruined Packer _____	
				Final Shut-In <u>120</u>	Mileage <u>X90</u>	<u>90</u>
				T-On Location <u>1100</u>	Sub Total: <u>1890</u>	
				T-Started <u>1200</u>	Std. By _____	
				T-Open <u>1720</u>	Other Fee <u>150</u>	
				T-Pulled <u>2155</u>	Total: <u>2040</u>	
				T-Out <u>2-02 2100</u>		

TRILOBITE TESTING INC. SHALL NOT BE LIABLE FOR DAMAGED OF ANY KIND OF THE PROPERTY OR PERSONNEL OF THE ONE FOR WHOM A TEST IS MADE, OR FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.

Approved By T. Michael Dodge
 Our Representative [Signature]



TRILOBITE TESTING, INC.

P.O. Box 362 • Hays, Kansas 67601

FLUID SAMPLER DATA

Ticket No. 22374 Date 1-30-08
Company Name Precor Western
Lease Darden Farms #3 Test No. 2
County Haskell, KS Sec. 15 Twp. 30S Rng. 32W

SAMPLER RECOVERY

Gas 0 ML Chlorides _____ ppm.
Oil 0 ML Resistivity _____ ohms @ _____ F
Mud 3000 ML Viscosity _____
Water 1000 ML Mud Weight _____
Other 0 ML Filtrate _____
Pressure 350 # ML Other _____
Total 4000 ML _____

PIT MUD ANALYSIS

SAMPLER ANALYSIS

Resistivity 1331 ohms @ 73 F
Chlorides 25,000 ppm.
Gravity _____ corrected @60F

PIPE RECOVERY

TOP
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

MIDDLE
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

BOTTOM
Resistivity 1334 ohms @ 74 F
Chlorides 25,000 ppm.

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.





CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.





DRILL STEM TEST REPORT

Prepared For: **Presco Western**

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

15/30S/32W

Daiden Farms #3

Start Date: 2006.02.03 @ 19:05:43

End Date: 2006.02.04 @ 10:22:26

Job Ticket #: 22375 DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Presco Western

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

Daiden Farms #3

15/30S/32W

Job Ticket: 22375

DST#: 3

Test Start: 2006.02.03 @ 19:05:43

GENERAL INFORMATION:

Formation: **Marmaton B**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 23:29:11

Time Test Ended: 10:22:26

Test Type: **Conventional Bottom Hole**

Tester: **Dustin Rash**

Unit No: **20**

Interval: **4878.00 ft (KB) To 4900.00 ft (KB) (TVD)**

Total Depth: **4900.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2082.00 ft (KB)**

2077.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 6798

Inside

Press@RunDepth: **259.71 psig @ 4880.00 ft (KB)**

Start Date: **2006.02.03**

End Date:

2006.02.04

Start Time: **19:05:43**

End Time:

10:22:26

Capacity: **7000.00 psig**


Last Calib.: **1899.12.30**

Time On Btm: **2006.02.03 @ 23:26:11**

Time Off Btm: **2006.02.04 @ 04:13:56**

TEST COMMENT: IF- Fair building blow . Built to 7 inches.
IS- No blow back.
FF- Fair building blow . Built to 5 inches.
FS- No blow back.

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2307.88	117.50	Initial Hydro-static
3	18.40	116.95	Open To Flow (1)
35	123.69	130.64	Shut-In(1)
97	1467.91	125.89	End Shut-In(1)
98	127.36	126.40	Open To Flow (2)
156	259.71	133.79	Shut-In(2)
283	1459.59	129.75	End Shut-In(2)
288	2330.35	126.65	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
84.00	100% Mud	0.41
196.00	30% Mud 70% Water	0.96
202.00	5% Mud 95% Water	0.99

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Presco Western

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

Daiden Farms #3

15/30S/32W

Job Ticket: 22375

DST#: 3

Test Start: 2006.02.03 @ 19:05:43

Tool Information

Drill Pipe:	Length: 4266.00 ft	Diameter: 3.80 inches	Volume: 59.84 bbl	Tool Weight: 2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 22000.00 lb
Drill Collar:	Length: 596.00 ft	Diameter: 2.25 inches	Volume: 2.93 bbl	Weight to Pull Loose: 15000.00 lb
		Total Volume:	62.77 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	14.00 ft			String Weight: Initial 78000.00 lb
Depth to Top Packer:	4878.00 ft			Final 82000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	22.00 ft			
Tool Length:	52.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		


Tool Comments:

Tool Description

Length (ft) Serial No. Position Depth (ft) Accum. Lengths

Change Over Sub	1.00			4849.00	
Shut In Tool	5.00			4854.00	
Sampler	3.00			4857.00	
HMV	5.00			4862.00	
Jars	5.00			4867.00	
Safety Joint	2.00			4869.00	
Packer	5.00			4874.00	30.00 Bottom Of Top Packer
Packer	4.00			4878.00	
Stubb	1.00			4879.00	
Perforations	1.00			4880.00	
Recorder	0.00	6798	Inside	4880.00	
Perforations	17.00			4897.00	
Recorder	0.00	10993	Inside	4897.00	
Bullnose	3.00			4900.00	22.00 Bottom Packers & Anchor

Total Tool Length: 52.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Presco Western

Daiden Farms #3

5480 Valmont Ste 350
Boulder CO 80301

15/30S/32W

Job Ticket: 22375

DST#: 3

ATTN: Mike Dodge

Test Start: 2006.02.03 @ 19:05:43

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity: 225000 ppm

Viscosity: 43.00 sec/qt

Cushion Volume:

bbl

Water Loss: 12.77 in³

Gas Cushion Type:

Resistivity: 0.08 ohm.m

Gas Cushion Pressure:

psig

Salinity: 17500.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
84.00	100% Mud	0.413
196.00	30% Mud 70% Water	0.964
202.00	5% Mud 95% Water	0.993

Total Length: 482.00 ft

Total Volume: 2.370 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:


Serial #: 6798


Inside

Presco Western

15/30S32W

DST Test Number: 3





DRILL STEM TEST REPORT

Prepared For: **Presco Western**

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

15/30S/32W

Daiden Farms #3

Start Date: 2006.02.05 @ 20:44:01

End Date: 2006.02.06 @ 13:01:29

Job Ticket #: 22951 DST #: 4

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Presco Western

5480 Valmont Ste 350
Boulder CO 80301

ATTN: Mike Dodge

Daiden Farms #3

15/30S/32W

Job Ticket: 22951

DST#: 4

Test Start: 2006.02.05 @ 20:44:01

GENERAL INFORMATION:

Formation: **Atoka**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 02:06:29

Time Test Ended: 13:01:29

Test Type: **Conventional Bottom Hole**

Tester: **Dustin Rash**

Unit No: **20**

Interval: **5276.00 ft (KB) To 5328.00 ft (KB) (TVD)**

Total Depth: **5328.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2082.00 ft (KB)**

2077.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 6798

Inside

Press@RunDepth: **45.95 psig @ 5279.00 ft (KB)**

Start Date: **2006.02.05**

End Date:

2006.02.06

Start Time: **20:44:01**

End Time:

13:01:29

Capacity: **7000.00 psig**


Last Calib.: **1899.12.30**

Time On Btm: **2006.02.06 @ 02:03:59**

Time Off Btm: **2006.02.06 @ 06:50:59**

TEST COMMENT: F-Weak blow . Built to 1/4 inch.
ISI-No blow back.
FF-Fair building blow . Built to 7 inches.
FSI-No blow back.

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2573.68	124.24	Initial Hydro-static
3	35.46	123.80	Open To Flow (1)
19	40.75	125.12	Shut-In (1)
81	169.32	127.71	End Shut-In (1)
84	30.60	127.59	Open To Flow (2)
141	45.95	129.25	Shut-In (2)
270	258.04	131.45	End Shut-In (2)
287	2591.11	133.00	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
95.00	5% Gas 95% Mud	0.47

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Presco Western

Daiden Farms #3

5480 Valmont Ste 350
Boulder CO 80301

15/30S/32W

Job Ticket: 22951

DST#: 4

ATTN: Mike Dodge

Test Start: 2006.02.05 @ 20:44:01


Tool Information

Drill Pipe:	Length: 4672.00 ft	Diameter: 3.80 inches	Volume: 65.54 bbl	Tool Weight: 2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 21000.00 lb
Drill Collar:	Length: 596.00 ft	Diameter: 2.25 inches	Volume: 2.93 bbl	Weight to Pull Loose: 20000.00 lb
			Total Volume: 68.47 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	22.00 ft			String Weight: Initial 73000.00 lb
Depth to Top Packer:	5276.00 ft			Final 75000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	52.00 ft			
Tool Length:	82.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			5247.00	
Shut In Tool	5.00			5252.00	
Sampler	3.00			5255.00	
Hydraulic tool	5.00			5260.00	
Jars	5.00			5265.00	
Safety Joint	2.00			5267.00	
Packer	5.00			5272.00	30.00 Bottom Of Top Packer
Packer	4.00			5276.00	
Stubb	1.00			5277.00	
Perforations	1.00			5278.00	
Change Over Sub	1.00			5279.00	
Recorder	0.00	6798	Inside	5279.00	
Drill Pipe	31.00			5310.00	
Change Over Sub	1.00			5311.00	
Perforations	14.00			5325.00	
Recorder	0.00	10993	Inside	5325.00	
Bullnose	3.00			5328.00	52.00 Bottom Packers & Anchor
Total Tool Length:		82.00			



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Presco Western

Daiden Farms #3

5480 Valmont Ste 350
Boulder CO 80301

15/30S/32W

Job Ticket: 22951

DST#: 4

ATTN: Mike Dodge

Test Start: 2006.02.05 @ 20:44:01

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

24500 ppm

Viscosity: 51.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.59 in³

Gas Cushion Type:

Resistivity: 0.32 ohm.m

Gas Cushion Pressure:

psig

Salinity: 6000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
95.00	5% Gas 95% Mud	0.467

Total Length:

95.00 ft

Total Volume:

0.467 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Serial #: 6798


Inside


Presco Western

15/30S/32W

DST Test Number: 4

Pressure vs. Time





TRILOBITE TESTING INC.

P.O. Box 362 • Hays, Kansas 67601

8394

No 22373

Test Ticket

Well Name & No. Darden Farms #3 Test No. 1 Date 1-28-06
 Company Presco Western Zone Tested Lansing
 Address _____ Elevation 2082 KB 2077 GL
 Co. Rep / Geo. Mike Dodge Cont. _____ Est. Ft. of Pay _____ Por. _____ %
 Location: Sec. 15 Twp. 30S Rge. 32W Co. Haskell State KS
 No. of Copies _____ Distribution Sheet (Y, N) _____ Turnkey (Y, N) _____ Evaluation (Y, N) _____

Interval Tested 4504-4528 Initial Str Wt./Lbs. 68K Unseated Str Wt./Lbs. 76K
 Anchor Length 24' 42' YP Wt. Set Lbs. 20K Wt. Pulled Loose/Lbs. 35K
 Top Packer Depth 4499 Tool Weight 2K
 Bottom Packer Depth 4504 Hole Size 7 7/8" Rubber Size 6 3/4"
 Total Depth 4570 Wt. Pipe Run N/A Drill Collar Run 596
 Mud Wt. 9.3 LCM 2" Vis. 35 WL 12.0 Drill Pipe Size 4.5X4 Ft. Run _____
 Blow Description IF - Fair building blow. Built to 13"
IS - No blowback
EF - Fair building blow. Built to BB in 53 min.
FS - No blowback

Recovery - Total Feet 596 GIP 0 Ft. in DC 596 Ft. in DP 0
 Rec. 283 Feet of Muddy Water %gas _____ %oil 85 %water 15 %mud _____
 Rec. 283 Feet of Muddy Water %gas _____ %oil 90 %water 10 %mud _____
 Rec. 30 Feet of Mud %gas _____ %oil _____ %water 100 %mud _____
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud _____
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud _____
 BHT 123 °F Gravity _____ °API D @ _____ °F Corrected Gravity _____ °API
 RW 1087 @ 58 °F Chlorides 105,000 ppm Recovery _____ Chlorides 3200 ppm System

(A) Initial Hydrostatic Mud	<u>2412</u> PSI	Recorder No. <u>6770 (2350)</u>	Test <u>Spindle</u> <u>1100</u>
(B) First Initial Flow Pressure	<u>84</u> PSI	(depth) _____	Jars <u>✓</u> <u>200</u>
(C) First Final Flow Pressure	<u>156</u> PSI	Recorder No. <u>10993</u>	Safety Jt. <u>✓</u> <u>50</u>
(D) Initial Shut-In Pressure	<u>1339</u> PSI	(depth) _____	Circ Sub <u>✓</u> <u>NIC</u>
(E) Second Initial Flow Pressure	<u>199</u> PSI	Recorder No. <u>13761</u>	Sampler <u>✓</u> <u>200</u>
(F) Second Final Flow Pressure	<u>329</u> PSI	(depth) _____	Straddle <u>✓</u> <u>250</u>
(G) Final Shut-In Pressure	<u>1345</u> PSI	Initial Opening <u>30</u>	Ext. Packer _____
(Q) Final Hydrostatic Mud	<u>2160</u> PSI	Initial Shut-In <u>60</u>	Shale Packer _____
		Final Flow <u>60</u>	Ruined Packer _____
		Final Shut-In <u>120</u>	Mileage <u>X90</u> <u>90</u>
		T-On Location <u>2015</u>	Sub Total <u>1890.00</u>
		T-Started <u>0145</u>	Std. By <u>X</u> <u>11.5</u>
		T-Open <u>0735</u>	Other _____
		T-Pulled <u>1210</u>	Total <u>2652.00</u>
		T-Out <u>1745</u>	

TRILOBITE TESTING INC. SHALL NOT BE LIABLE FOR DAMAGED OF ANY KIND OF THE PROPERTY OR PERSONNEL OF THE ONE FOR WHOM A TEST IS MADE, OR FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.

Approved By Mike Dodge
 Our Representative [Signature]

AECS \$150
 \$2652.50



TRILOBITE TESTING, INC.

P.O. Box 362 • Hays, Kansas 67601

FLUID SAMPLER DATA

Ticket No. 22373 Date 1-28-06
Company Name Presco Western
Lease Darden Farms #3 Test No. 1
County Haskell, KS Sec. 15 Twp. 30S Rng. 32W

SAMPLER RECOVERY

Gas 0 ML Chlorides _____ ppm.
Oil 0 ML Resistivity _____ ohms @ _____ F
Mud 500 ML Viscosity _____
Water 3500 ML Mud Weight _____
Other 0 ML Filtrate _____
Pressure 400# ML Other _____
Total 4000 ML _____

PIT MUD ANALYSIS

SAMPLER ANALYSIS

Resistivity 1.088 ohms @ 57 F
Chlorides 105,000 ppm.
Gravity _____ corrected @60F

PIPE RECOVERY

TOP
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

MIDDLE
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

BOTTOM
Resistivity 1.087 ohms @ 58 F
Chlorides 105,000 ppm.

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.






CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.





TRILOBITE TESTING INC.

P.O. Box 362 • Hays, Kansas 67601

No 22374

9/04

Test Ticket

Well Name & No. <u>Darden Farms #3</u>	Test No. <u>2</u>	Date <u>1-30-06</u>
Company <u>Presco Western</u>	Zone Tested <u>KC 'A'</u>	
Address _____	Elevation <u>2082</u> KB <u>2077</u> GL	
Co. Rep / Geo. <u>Mike Dodge</u>	Cont. _____	Est. Ft. of Pay _____ Por. _____ %
Location: Sec. <u>15</u> Twp. <u>30S</u> Rge. <u>32W</u> Co. <u>Haskell</u> State <u>KS</u>		
No. of Copies _____	Distribution Sheet (Y, N) _____	Turnkey (Y, N) _____ Evaluation (Y, N) _____

Interval Tested <u>4688-4718</u>	Initial Str Wt./Lbs. <u>77K</u>	Unseated Str Wt./Lbs. <u>81K</u>
Anchor Length <u>30'</u>	Wt. Set Lbs. <u>20K</u>	Wt. Pulled Loose/Lbs. <u>35K</u>
Top Packer Depth <u>4683</u>	Tool Weight <u>2K</u>	
Bottom Packer Depth <u>4688</u> <u>4718 S.P.</u>	Hole Size <u>7 7/8"</u>	Rubber Size <u>6 3/4"</u>
Total Depth <u>4770</u> <u>52' TP</u>	Wt. Pipe Run <u>N/A</u>	Drill Collar Run <u>596</u>
Mud Wt. <u>8.9</u> LCM <u>403#</u> Vis. <u>41</u> WL <u>12.4</u>	Drill Pipe Size <u>4.5X4</u>	Ft. Run _____
Blow Description <u>IF- Weak surface blow.</u>		

<u>IF- No blow back</u>	<u>lost electronic recorder in hole</u>
<u>FF- No blow</u>	
<u>FSI- No blow back</u>	

Recovery - Total Feet <u>114</u> GIP _____	Ft. in DC _____	Ft. in DP _____
Rec. <u>114</u> Feet of <u>water/mud</u>	%gas _____ %oil _____	%water <u>20</u> %mud <u>80</u>
Rec. _____ Feet of _____	%gas _____ %oil _____	%water _____ %mud _____
Rec. _____ Feet of _____	%gas _____ %oil _____	%water _____ %mud _____
Rec. _____ Feet of _____	%gas _____ %oil _____	%water _____ %mud _____
Rec. _____ Feet of _____	%gas _____ %oil _____	%water _____ %mud _____

BHT _____ °F Gravity _____ °API D @ _____ °F Corrected Gravity _____ °API
RW <u>1331</u> @ <u>73</u> °F Chlorides <u>25000</u> ppm Recovery _____ Chlorides <u>9700</u> ppm System

(A) Initial Hydrostatic Mud <u>2291</u> AK-1 Alpine PSI Recorder No. <u>6770</u> Test <u>Straddle</u> <u>1100</u>
(B) First Initial Flow Pressure <u>56</u> PSI (depth) _____ Jars <u>✓</u> <u>200</u>
(C) First Final Flow Pressure <u>56</u> PSI Recorder No. <u>10993</u> Safety Jt. <u>✓</u> <u>50</u>
(D) Initial Shut-In Pressure <u>1341</u> PSI (depth) _____ Circ Sub <u>✓</u> <u>NIC</u>
(E) Second Initial Flow Pressure <u>79</u> PSI Recorder No. <u>13761</u> Sampler <u>✓</u> <u>200</u>
(F) Second Final Flow Pressure <u>90</u> PSI (depth) _____ Straddle <u>✓</u> <u>250</u>
(G) Final Shut-In Pressure <u>1331</u> PSI Initial Opening <u>30</u> Ext. Packer _____
(Q) Final Hydrostatic Mud <u>2154</u> PSI Initial Shut-In <u>60</u> Shale Packer _____

TRILOBITE TESTING INC. SHALL NOT BE LIABLE FOR DAMAGED OF ANY KIND OF THE PROPERTY OR PERSONNEL OF THE ONE FOR WHOM A TEST IS MADE, OR FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.	Final Flow <u>60</u>	Ruined Packer _____
Approved By <u>T. Michael Dodge</u>	Final Shut-In <u>120</u>	Mileage <u>X90</u> <u>90</u>
Our Representative <u>D. Kosh</u>	T-On Location <u>1100</u>	Sub Total: <u>1890</u>
	T-Started <u>1200</u>	Std. By _____
	T-Open <u>1720</u>	Other Fee <u>150</u>
	T-Pulled <u>2155</u>	Total: <u>2040</u>
	T-Out <u>2-02 2100</u>	



TRILOBITE TESTING, INC.

P.O. Box 362 • Hays, Kansas 67601

FLUID SAMPLER DATA

Ticket No. 22374 Date 1-30-08
Company Name Presco Western
Lease Darden Farms #3 Test No. 2
County Haskell, KS Sec. 15 Twp. 30S Rng. 32W

SAMPLER RECOVERY

Gas Ø ML Chlorides _____ ppm.
Oil Ø ML Resistivity _____ ohms @ _____ F
Mud 3000 ML Viscosity _____
Water 1000 ML Mud Weight _____
Other Ø ML Filtrate _____
Pressure 350 # ML Other _____
Total 4000 ML _____

PIT MUD ANALYSIS

SAMPLER ANALYSIS

Resistivity 331 ohms @ 73 F
Chlorides 25,000 ppm.
Gravity _____ corrected @60F

PIPE RECOVERY

TOP
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

MIDDLE
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

BOTTOM
Resistivity 1334 ohms @ 74 F
Chlorides 25,000 ppm.

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.





CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.





TRILOBITE TESTING INC.

P.O. Box 362 • Hays, Kansas 67601

No 22375

9/04

Test Ticket

Well Name & No. <u>Darden Fairs #3</u>	Test No. <u>3</u>	Date <u>2-3-06</u>
Company <u>Presco Western</u>	Zone Tested <u>Marmaton B'</u>	
Address _____	Elevation <u>2082</u> KB <u>2077</u> GL	
Co. Rep / Geo. <u>Mike Dodge</u>	Cont. _____	Est. Ft. of Pay _____ Por. _____ %
Location: Sec. <u>15</u> Twp. <u>30S</u> Rge. <u>32W</u> Co. <u>Haskell</u> State <u>KS</u>		
No. of Copies _____	Distribution Sheet (Y, N) _____	Turnkey (Y, N) _____ Evaluation (Y, N) _____

Interval Tested <u>4878-4900</u>	Initial Str Wt./Lbs. <u>78K</u>	Unseated Str Wt./Lbs. <u>82K</u>
Anchor Length <u>22'</u>	Wt. Set Lbs. <u>22K</u>	Wt. Pulled Loose/Lbs. <u>15K</u>
Top Packer Depth <u>4873</u>	Tool Weight <u>2K</u>	
Bottom Packer Depth <u>4878</u>	Hole Size <u>7 7/8"</u>	Rubber Size <u>6 3/4"</u>
Total Depth <u>4900</u>	Wt. Pipe Run <u>N/A</u>	Drill Collar Run <u>596</u>
Mud Wt. <u>8.75</u> LCM <u>3"</u> Vis. <u>43</u> WL <u>12.8</u>	Drill Pipe Size <u>4.5X4</u>	Ft. Run _____

Blow Description IF- Fair building blow. Built to 7 inches.
IS- No blowback.
FF- Fair building blow. Built to 5 inches.
FSE- No blowback.

Recovery - Total Feet <u>482</u>	GIP <u>0</u>	Ft. in DC <u>482</u>	Ft. in DP <u>0</u>
Rec. <u>84</u> Feet of <u>Mud</u>	%gas _____	%oil _____	%water <u>100</u> %mud _____
Rec. <u>196</u> Feet of <u>Muddy Water</u>	%gas _____	%oil <u>70</u>	%water <u>30</u> %mud _____
Rec. <u>202</u> Feet of <u>Muddy Water</u>	%gas _____	%oil <u>95</u>	%water <u>5</u> %mud _____
Rec. _____ Feet of _____	%gas _____	%oil _____	%water _____ %mud _____
Rec. _____ Feet of _____	%gas _____	%oil _____	%water _____ %mud _____

BHT 130 °F Gravity _____ °API D @ _____ °F Corrected Gravity _____ °API
 RW 1.078 @ 41 °F Chlorides 225,000 ppm Recovery _____ Chlorides 17,500 ppm System

(A) Initial Hydrostatic Mud	AK-1 <u>2308</u> PSI	Alpine _____	Recorder No. <u>6798</u>	Test <u>Conventional</u>
(B) First Initial Flow Pressure	<u>18</u> PSI	(depth) <u>4880</u>	Jars <u>✓</u>	<u>200</u>
(C) First Final Flow Pressure	<u>124</u> PSI	Recorder No. <u>10993</u>	Safety Jt. <u>✓</u>	<u>50</u>
(D) Initial Shut-In Pressure	<u>1468</u> PSI	(depth) <u>4897</u>	Circ Sub <u>✓</u>	<u>NIC</u>
(E) Second Initial Flow Pressure	<u>127</u> PSI	Recorder No. _____	Sampler <u>✓</u>	<u>200</u>
(F) Second Final Flow Pressure	<u>260</u> PSI	(depth) _____	Straddle _____	
(G) Final Shut-In Pressure	<u>1460</u> PSI	Initial Opening <u>30</u>	Ext. Packer _____	
(Q) Final Hydrostatic Mud	<u>2330</u> PSI	Initial Shut-In <u>60</u>	Shale Packer _____	

TRILOBITE TESTING INC. SHALL NOT BE LIABLE FOR DAMAGED OF ANY KIND OF THE PROPERTY OR PERSONNEL OF THE ONE FOR WHOM A TEST IS MADE, OR FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.

Approved By <u>Mike Dodge</u>	Final Flow <u>60</u>	Ruined Packer _____
Our Representative <u>Dustin Lash</u>	Final Shut-In <u>120</u>	Mileage <u>X90</u>
	T-On Location <u>1830</u>	Sub Total <u>81640.00</u>
	T-Started <u>1900</u>	Std. By <u>X6</u>
	T-Open <u>2330</u>	Other _____
	T-Pulled <u>0400</u>	Total <u>\$2990.00</u>
	T-Out <u>1000</u>	

\$1990



TRILOBITE TESTING, INC.

P.O. Box 362 • Hays, Kansas 67601

FLUID SAMPLER DATA

Ticket No. 22375 Date 2-3-06
Company Name Presco Western
Lease Darden Farm #3 Test No. 3
County Haskell, KS Sec. 15 Twp. 30S Rng. 32W

SAMPLER RECOVERY

Gas 0 ML Chlorides _____ ppm.
Oil 0 ML Resistivity _____ ohms @ _____ F
Mud 400 ML Viscosity _____
Water 3600 ML Mud Weight _____
Other 0 ML Filtrate _____
Pressure 350* ML Other _____
Total 4000 ML _____

PIT MUD ANALYSIS

SAMPLER ANALYSIS

Resistivity 1080 ohms @ 41 F
Chlorides 225,000 ppm.
Gravity _____ corrected @60F

PIPE RECOVERY


TOP
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.


MIDDLE
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.

BOTTOM
Resistivity 1078 ohms @ 41 F
Chlorides 225,000 ppm.

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.





TRILOBITE TESTING INC.

P.O. Box 362 • Hays, Kansas 67601

No 22951

Test Ticket

Well Name & No. Darden Farms #3 Test No. 4 Date 2-5-06
 Company Presco Western Zone Tested ~~Montez~~ ATOKA
 Address _____ Elevation 2082 KB 2077 GL
 Co. Rep / Geo. Mike Dodge Cont. _____ Est. Ft. of Pay _____ Por. _____ %
 Location: Sec. 15 Twp. 30S Rge. 32W Co. Haskell State KS
 No. of Copies _____ Distribution Sheet (Y, N) _____ Turnkey (Y, N) _____ Evaluation (Y, N) _____

Interval Tested 5276-5328 Initial Str Wt./Lbs. 73K Unseated Str Wt./Lbs. 75K
 Anchor Length 52' Wt. Set Lbs. 21K Wt. Pulled Loose/Lbs. 20K
 Top Packer Depth 5271 Tool Weight 2K
 Bottom Packer Depth 5276 Hole Size 7 7/8" ✓ Rubber Size 6 3/4" ✓
 Total Depth 5328 Wt. Pipe Run N/A Drill Collar Run 596
 Mud Wt. 8.9 LCM 5# Vis. 51 WL 7.6 Drill Pipe Size 4.5X4 Ft. Run 4672
 Blow Description IF- Weak blow. Built to 1/4 inch.
ISF- No blowback.
FF- Fair building blow. Built to 7 inches.
FSF- No blowback.

Recovery - Total Feet 95 GIP 240 Ft. in DC 95 Ft. in DP 0
 Rec. 95 Feet of Mud 5 %gas %oil %water 95 %mud
 Rec. _____ Feet of _____ %gas %oil %water %mud
 Rec. _____ Feet of _____ %gas %oil %water %mud
 Rec. _____ Feet of _____ %gas %oil %water %mud
 Rec. _____ Feet of _____ %gas %oil %water %mud
 BHT 131 °F Gravity _____ °API D @ _____ °F Corrected Gravity _____ °API
 RW 1321 @ 60 °F Chlorides 24,500 ppm Recovery _____ Chlorides 6000 ppm System

(A) Initial Hydrostatic Mud	<u>2574</u> PSI	Recorder No.	<u>6798 (2130)</u>	Test	<u>Conventional</u>
(B) First Initial Flow Pressure	<u>35</u> PSI	(depth)	<u>5279</u>	Jars	<u>✓</u> <u>200</u>
(C) First Final Flow Pressure	<u>41</u> PSI	Recorder No.	<u>10993</u>	Safety Jt.	<u>✓</u> <u>50</u>
(D) Initial Shut-In Pressure	<u>169</u> PSI	(depth)	<u>5325</u>	Circ Sub	<u>✓</u> <u>N/C</u>
(E) Second Initial Flow Pressure	<u>31</u> PSI	Recorder No.		Sampler	<u>✓</u> <u>200</u>
(F) Second Final Flow Pressure	<u>46</u> PSI	(depth)		Straddle	
(G) Final Shut-In Pressure	<u>258</u> PSI	Initial Opening	<u>15</u>	Ext. Packer	
(Q) Final Hydrostatic Mud	<u>2591</u> PSI	Initial Shut-In	<u>60</u>	Shale Packer	
		Final Flow	<u>60</u>	Ruined Packer	
		Final Shut-In	<u>120</u>	Mileage	<u>X90</u> <u>90</u>
		T-On Location	<u>2000</u>	Sub Total:	<u>1740</u>
		T-Started	<u>2145</u>	Std. By	<u>X07.75</u> <u>200</u>
		T-Open	<u>0250</u>	Other	
		T-Pulled	<u>0710</u>	Total	<u>\$3240.00</u> <u>281.25</u>
		T-Out	<u>1345</u>		<u>\$2221.25</u>

TRILOBITE TESTING INC. SHALL NOT BE LIABLE FOR DAMAGED OF ANY KIND OF THE PROPERTY OR PERSONNEL OF THE ONE FOR WHOM A TEST IS MADE, OR FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.

Approved By Mike Dodge
 Our Representative Dustin Lash



TRILOBITE TESTING, INC.

P.O. Box 362 • Hays, Kansas 67601

FLUID SAMPLER DATA

Ticket No. 22951 Date 2-5-06
Company Name Presco Western
Lease Darden Farms #3 Test No. 4
County Haskell, KS Sec. 15 Twp. 30S Rng. 32W

SAMPLER RECOVERY

Gas 13 cubic Feet ML
Oil Ø ML
Mud 3500 ML
Water Ø ML
Other Ø ML
Pressure 350* ML
Total 3500 ML

PIT MUD ANALYSIS

Chlorides _____ ppm.
Resistivity _____ ohms @ _____ F
Viscosity _____
Mud Weight _____
Filtrate _____
Other _____

SAMPLER ANALYSIS

Resistivity 1,308 ohms @ 60 F
Chlorides 25,500 ppm.
Gravity _____ corrected @60F

PIPE RECOVERY

TOP
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.
MIDDLE
Resistivity _____ ohms @ _____ F
Chlorides _____ ppm.
BOTTOM
Resistivity 321 ohms @ 60 F
Chlorides 24,500 ppm.