

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


28-30-33W

Company- CITIES SERVICE OIL COMPANY
Farm- Hickman "B" No. 1

SEC. 28 T. 30 R. 33W
SE SE SE NW
100' N. & 100' W. of Center

Total Depth. 2795
Comm. 9-22-49 Comp. 9-29-49
Shot or Treated.
Contractor. Lohmann & Johnson Drlg. Co.
Issued. 5-30-53

County Haskell
KANSAS



CASING:

8 5/8" 645' cem. w/300 sx
5 1/2" 2786' cem. w/700 sx

Elevation. 2942

Production. 14,400,000 Gas
R.P. 390#

Figures Indicate Bottom of Formations.

soil & surface	60
sand & gravel	300
sand & shale	620
red bed	755
shale & shells	1175
anhydrite	1260
shale	1512
red bed & shale	1560
shale	1845
shale & shells	1975
shale & lime	2055
lime & shale	2240
shale & lime	2320
lime & shale	2795
Total Depth	

Tops:
Herington 2608
Upper Krider 2637
Lower Krider 2660
Winfield 2706
Upper Ft. Riley 2758

Perf. 80 shots 2638-54
140 shots 2666-94
110 shots 2708-30