

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


30-30-33W

Company - STANOLIND OIL AND GAS COMPANY
Farm - Wilson Gas U. "C" No. 1

SEC. 30 T. 30 R. 33W
SE SE NW
150' NSL, 150' WEL of NW/4

Total Depth. 2775
Comm. 4-2-50 Comp. 4-20-50
Shot or Treated. 9000 gals 15%.
Contractor.
Issued. 6-17-50

County. Haskell
KANSAS



Elevation. 2955.9m

Production. 9,978,000 gas

CASING:

10 3/4" 658' cem w/500 sx.
7" 2731' cem w/300 sx.

Figures Indicate Bottom of Formations.

clay	90
sand	540
clay, sand	630
red bed	1460
red rock	1710
anhydrite	1780
shale, anhyd.	1980
anhyd., shale, gyp	2160
red rock, anhyd.	2300
anhyd., shale	2443
anhyd., lime	2540
lime, anhyd., shale	2593
anhyd., lime	2620
lime, shale	2688
lime	2775
Total depth	

Tops:
Hollenberg 2547-2555
Herington 2576-2600
Krider 2610-2674
Winfield 2695-2722
Towanda 2731-2775

Schlumberger ran elec. log.