

32-30-33W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.  
Farm - Conover "A" No. 1

SEC. 32 T. 30 S. 33W  
NE NE SW  
100' S, 100' W of center

Total Depth. 2770  
Comm. 6-3-49 Comp. 6-11-49  
Shot or Treated. acid  
Contractor. Lohmann Johnson Drlg.  
Issued. 2-11-50

County. Haskell  
KANSAS



Elevation. 2952 Ind.

Production. Init. 16,300,000 gas

Figures Indicate Bottom of Formations.

sand, shale	385
shale	610
sand	620
red bed	780
anhydrite	800
shale	1160
anhydrite	1225
shale, sand	1500
shale	1600
salt, shale	1757
lime	1785
salt, lime	1895
lime, shale	1910
redbed, shale	2010
shale, shels	2240
lime	2337
lime, shale	2614
lime	2762
shale	2770
Total depth	

Tops:	
Herington	2562
Upper Krider	2592
Lower "	2614
Winfield	2663
Upper Ft. Riley	2708

Perforating record:  
210 shots 2702-44  
100 shots 2660-80  
150 shots 2616-46  
60 shots 2594-2606

acid record:  
6-16-49, 1000 gals 15% acid 2594-2606  
" 1500 gals 15% acid 2616-46  
" 1250 gals 15% acid 2660-80  
" 2250 gals 15% acid 2702-44  
6-17-49 14000 gals 15% acid 2594-2680  
" 8000 gals 15% acid 2702-44  
6-19-49 9000 gals 5% acid to all zones

Initial Prd. 20 min OF 16,300 MCF,

