

31-30-33W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas


Company - CITIES SERVICE OIL CO.
Farm - Thompson "B" No. 1

SEC. 31 T. 30 R. 33W
NE NE SW
100' S & 100' W of Center

Total Depth. 2770'
Comm. 6-16-48 Comp. 6-24-48
Shot or Treated. Acid. 28,000 gals.
Contractor. Corbott-Barbour Drlg. Co.
Issued. 12-18-48

County. Haskell

KANSAS



Elevation. 2952 Ind.

Production. 10,100,000 gas

CASING:

8-5/8" 640' Cem. W/300 Sx.
5-1/2" 2769' Cem. W/900 Sx.
5 1/2" 2704' from ground.

Figures Indicate Bottom of Formations.

sand & clay	425
sand & shells	550
red rock	850
red beds & shale	1145
shale & shells	1590
shale	1775
shale & lime	1920
shale	2085
shale & lime	2260
lime & shale	2460
lime	2520
lime & shale	2770
Total Depth	

Scalumberger Elec. Log.

Tops:	
Herrington	2565
Upper Krider	2596
Lower Krider	2616
Winfield	2662
Upper Ft. Riley	2722

Perf 220 shots 2708-52

7-13-48 2,000 gals. 15% acid 2708-52
7-14-48 9,000 gals. 15% acid 2708-52

1,830 MCF gas 2708-52.

Perf. 110 shots 2662-84
Perf. 140 shots 2620-48
Perf. 70 shots 2596-2610.

7-17-48 1,000 gals. 15% acid 2596-2648
" " " " " 2662-84
7-18-48 12,000 gals. 15% acid 2596-2684
7-20-48 9,000 gals. 5% acid to all zones.