

33 - 30 - 34 W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - THE TREES OIL COMPANY
Farm - C. G. Dennis No. 1

SEC. 33 T. 30 R. 34W
CSW/4

Total Depth. 2558
Comm. 12-22-47 Comp. 1-11-48
Shot or Treated.
Contractor. Walter Kuhn Drlg. Co.
Issued. 12-31-49

County. Haskell
KANSAS



CASING:
10 3/4" 463.23' cem w/325 sx. Circ.
7" 2389'9" cem w/700 sx., circ.
5 1/2" liner 199'2"

Elevation. 2910 rh
2810 Ind
Production. Open flow 23,000,000
gas

Figures indicate Bottom of Formations.

surface	50
sand,, gravel	220
clay, sand	290
clay blue	420
clay	448
red bed	483
red bed, gyp	715
shale, gyp	1085
shale, sand, shells	1425
redbed, shells	1610
shale, gyp	1906
red bed, gyp	1995
shale, gyp	2063
lime brkn	2135
lime brkn, shale	2180
anhydrite, shale, lime	2235
anhydrite, lime	2295
anhydrite, lime, shale	2375
anhydrite, lime RTD	2400
lime	2468
shale	2473
lime	2510
shale, lime	2532
lime	2558
Total Depth	