

22-30-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PAN AMERICAN PET. CORP.
Farm- Hague No. 1

SEC. 22 T. 30 R. 34W
CE/2 W/2 SE NE
1980' SNL 810' WEL NE/4

Total Depth. 5900' PB 4710'
Comm. 6-12-64 Comp. 8-7-64
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 10-31-64

County Haskell
KANSAS



Elevation. 2937' R.B.

Production. DRY

CASING:

8 5/8" 1762' w/1250 sx cem.
5 1/2" 4815' w/175 sx cem.

Figures Indicate Bottom of Formations.

sand, red bed	1200
sand, lime	1350
shale, lime	1697
shale, lime, anhydrite	1775
lime, shale	3160
lime	3370
lime, shale	3738
lime, chalk	3915
lime, shale	4310
lime	4550
lime, shale	4645
lime	5516
lime, chert	5540
lime	5795
lime, chert	5875
lime	5900
Total Depth	5900
PB	4710

TOPS: SCOUT	
Council Grove	2831
Pennsylvanian	3224
Toronto	4003
Missourian	4050
Lansing "A"	4084
Lansing "B"	4140
Lansing "F"	4349
Kansas City "A"	4530
Kansas City "B"	4592
Des Moines	4687
St. Geneva	5300
St. Louis	5412
Salem	5589

OIL OR GAS SANDS OR ZONES

Lansing "A"	4084-4140
Lansing "B"	4140-4349

Kansas City "A"	4530-4592
Kansas City "B"	4592-4687
Des Moines	4687-5192
Morrow	5192-5300

