

9-69W Map No. *K-83*

OPER SATURN OIL & GAS CO. - Cheyenne,
Wyoming

WELL #2 PARSONS "B"
MORAN Brothers

FIELD Panoma Pool (C Gr Gas)

I.P. 4 Pt Cal OF 8,000,000 Cfgpd, CG 2738-2843



S-T-R 34-30S-37W
SPOT C NW SE
CO GRANT (Ks)
ELEV 3032 GR

(GR Log)	
Winf	2481 / 551
CG	2718 / 314
Adm	2956 / 76
LTD	2988 / 44
RTD	3000 / 32

No DST's, No Cores, RTD 3000, Ran Log, LTD 2988, 5"
@2990 w/200 sx.

Pf 12/2738-41, 20/2752-62, 24/2798-2804, 18/
2819-28, 4/2841-43 (CG), 8 dry, no sho/4 hrs, 3000A,
Flo 648,000 Cfgpd & 10 BLW/PH/2 hrs, 9 hr BD Ga
828,000 Cfgpd & 1 BLW/PH (CG), Frac 80,000 gal wtr x
60,000# sd, 3 hr BD Ga 17,950,000 Cfgpd, 7 hr BD Ga
9,037,000 Cfgpd, wet w/ld, Ran 1 1/2" tbg @2752, had 2 hr
BD Ga 8,082,000 Cfgpd, 2 3/4 hr BD Ga 8,937,000 Cfgpd,
4 Pt Cal OF; 8,000,000 CFGPD, SICP 279.4#, SITP 279.4#
CG 2738-2843 - COMPLETED on 8-25-65

Data Inc

P-S 3034 EDF
3032 GL

MISCELL DATA	GEOI _____	ELEV <u>3045 KB</u>	SPUD DATE <u>6-19-65</u>
	FTG _____	<u>3042 DF</u>	DRLG COMP _____
	SUPPT _____		FR by DATA <u>5-5-65</u>
	CSG <u>8" @645 w/400 sx, 5" @2990 w/200 sx.</u>		COMP by " <u>9-2-65</u>

Liberal Electric Log Log

3032 Rk

Win 2482 (+550)

C. G. 2734 (+298) + 8,000 mcf

TD 2988