


2-201W MAP NO. 82 SEC. 35-308-42W
 STATE Kans. COUNTY Stanton LOC. C SW/4
 OPER. The Superior Oil Co., Casper, Wyoming FT/FR _____ LINE _____
 WELL #2 FARM Weaver Unit FT/FR _____ LINE _____
 SPARKS ELEV. 3488 GR. 3496 DF 3498 KB _____
 Lohmann & Johnson Tools GEOL. _____
 CO. INT. 5350' Morr test
 F.R. 11/18/63 SPUD 12/3/63 COMP. 2/25/64
 TD. 5258 FM. Keyes PBTD. _____
 COMP. RECORD 8-5/8" @ 1518 w/700 sx.
Temp. Abd. - D & A *3/4/65* *Data Inc.*



KB Log Tops:

Lans	3642 - 144	Mrw sd	5125 -1627	LTD	5255 -1757
Cher	4539 -1041	Keyes	5205 -1707	RTD	5258 -1760

DST #1 (Keyes) 5233-58, Op 3", Op 1 hr., GTS/4", R 140' GCM,
360' Sli slty mdy wtr, ISIP 1025#/30", IFP 85#, FFP 164#,
FSIP 955#/30",
RTD 5258, Log, 4½" @ 5258 w/200 sx., Pf 16/5216-20, 88/5224-46
(Keyes) 500 MA, \$ 1d, \$ 86 BSW/NT, clor 22,000 PPM, SD, MICT,
q all perfs w/75 sx., CO 5236, 16/5216-20, 24/5222-30 (Keyes)

2-3/8" tbg, \$ Pf 1d w/SSG, 200 MA, \$ pt 1d w/SSG, \$ 30 B Ld
9 hrs, 5200' from surface, \$ 24 BW (no gas) 1½ hrs, \$ 9 BW/2 hrs
Temp. Abd. (2/17/64) COMPLETE

\$ 86 A 3/4/65

AMARILLO ELECTRIC LOG TOPS

3498 KB

Council Grove 2445 (+1053) ~~2445~~
Heebner 3536 (-38)
Toronto 3560 (-62)
Lansing 3643 (-145)
Marmaton 4180 (-682)
Morrow 4834 (-1336)
Keyes 5183 (-1685) 2/13
Keyes 5205 (-1707) 34+/48+; \$ XW
RTD 5258 D & A

Top 3122 + 376

CR